

ATTACHMENT F

PLAN


PROJECT PARCEL SITE CITY OF BATH ASSESSOR'S MAP & LOT NUMBERS

Applicant:

CITY OF BATH 55 FRONT STREET BATH, ME 04530

Current Owner of Record:

CITY OF BATH 55 FRONT STREET BATH, ME 04530



BATH FIRE HEADQUARTERS

826 HIGH STREET, BATH, MAINE

PREPARED BY:



Relationships. Responsiveness. Results. www.gorrillpalmer.com 207.772.2515

GENERAL NOTES

GENERAL NOTES

1. TOPOGRAPHIC DATA AND EXISTING CONDITIONS WAS PREPARED BY SEBAGO TECHNICS OF SOUTH PORTLAND, MAINE ON 07/26/2024.

2. THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND OR THE FLEVATION OF THE EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND WHERE POSSIBLE MEASUREMENTS TAKEN IN THE FIELD. THIS INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL THE APPROPRIATE UTILITY COMPANY AND DIG SAFE AT LEAST 72 HOURS PRIOR TO ANY EXCAVATION TO REQUEST EXACT FIELD LOCATION OF UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS.

3. MAINTENANCE OF EROSION CONTROL MEASURES IS OF PARAMOUNT IMPORTANCE TO THE OWNER AND THE CONTRACTOR IS RESPONSIBLE FOR PLANS. ADDITIONAL EROSION CONTROL MEASURES SHALL BE INSTALLED IF DEEMED NECESSARY BY ON-SITE INSPECTIONS OF THE OWNER, THE CITY OF BATH OR THEIR REPRESENTATIVES AT NO ADDITIONAL COST TO

4. ALL MATERIAL SCHEDULES SHOWN ON THE PLANS ARE FOR GENERAL INFORMATION ONLY. THE CONTRACTOR SHALL PREPARE HIS OWN MATERIAL SCHEDULES BASED UPON HIS PLAN REVIEW. ALL SCHEDULES ORDERING MATERIALS OR PERFORMING WORK.

5. ALL MATERIALS AND CONSTRUCTION METHODS SHALL CONFORM TO MAINEDOT SPECIFICATIONS, AND/OR CITY OF BATH SPECIFICATIONS.

PERMITTING NOTES

I. THIS PROJECT IS SUBJECT TO THE TERMS AND CONDITIONS OF A SITE PLAN APPROVAL FROM THE CITY OF BATH. THE CONSTRUCTION WILL BE GOVERNED BY THE CITY OF BATH ZONING ORDINANCE WHICH IS AVAILABLE FOR VIEWING AT THE OFFICE OF THE ENGINEER OR THE MUNICIPAL OFFICE.

2. THIS PROJECT IS SUBJECT TO THE TERMS AND CONDITIONS OF A STORMWATER PERMIT FROM MAINE DEPARTMENT OF ENVIRONMENTAL PROTECTION. 3. THE CONTRACTOR SHALL REVIEW THE ABOVE REFERENCED PERMITS PRIOR

TO SUBMITTING A BID FOR THIS PROJECT, AND INCLUDE COSTS AS NECESSARY

TO COMPLY WITH THE CONDITIONS OF THESE PERMITS.

LAYOUT NOTES

- ALL DIMENSIONING, UNLESS NOTED OTHERWISE, IS TO THE FACE OF CURB.
- PIPE LENGTH EQUALS THE CENTER TO CENTER DISTANCES BETWEEN CATCH BASINS AND/OR MANHOLES MINUS ONE-HALF OF THE DIAMETER OF EACH CATCH BASIN OR MANHOLE.
- PROPERTY LINE AND R.O.W. MONUMENTS SHALL NOT BE DISTURBED BY CONSTRUCTION. IF DISTURBED, THEY SHALL BE RESET TO THEIR ORIGINAL LOCATIONS AT THE CONTRACTOR'S EXPENSE, BY A MAINE LICENSED LAND SURVEYOR.
- CURB RADII UNLESS OTHERWISE NOTED ON THE PLAN SHALL BE A MINIMUM OF 3'.

 ALL WATER UTILITY MATERIALS AND INSTALLATION METHODS SHALL CONFORM TO BATH WATER DISTRICT STANDARDS. ALL WATER DISTRIBUTION PIPING SHALL BE CLASS 52 DUCTILE IRON PIPE, DOUBLE CEMENT LINED AND BITUMINOUS COATED CONFORMING TO AWWA/ANSI C104/A21.4. DISINFECTION OF WATER LINES SHALL CONFORM TO AWWA STANDARD C651, LATEST REVISION.

2. THE LOCATION OF THE PROPOSED UNDERGROUND ELECTRICAL SERVICE IS APPROXIMATE AND THE CONTRACTOR SHALL COORDINATE THE EXACT LOCATION WITH CENTRAL MAINE POWER COMPANY.

3. THRUST BLOCKS OR LOCKING RETAINER GLANDS SHALL BE PLACED ON THE WATER DISTRIBUTION LINES AT ALL BENDS, TEES, VALVES, CHANGES IN DIRECTION, ETC. THE THRUST BLOCKS OR LOCKING RETAINER GLANDS SHALL MEET THE REQUIREMENTS OF THE BATH WATER DISTRICT STANDARDS.

ADVANCE OF THE START OF CONSTRUCTION OR ORDERING OF MATERIALS. TEST PIT INFORMATION SHALL BE PROMPTLY PROVIDED TO ENGINEER FOR REVIEW. 5. ALL GAS UTILITY MATERIALS AND INSTALLATION METHODS SHALL CONFORM

4. TEST PITS AT ALL UTILITY CROSSINGS SHALL BE COMPLETED TWO WEEKS IN

GRADING AND DRAINAGE NOTES

TO MAINE NATURAL GAS STANDARDS.

1. UNLESS OTHERWISE NOTED, ALL STORM DRAIN PIPE SHALL BE IN ACCORDANCE WITH MAINEDOT SPECIFICATIONS SECTION 603—— PIPE CULVERTS AND STORM DRAINS, LATEST REVISION WITH THE EXCEPTION THAT THE ONLY ACCEPTABLE TYPES OF PIPE ARE AS FOLLOWS, UNLESS OTHERWISE NOTED ON

> REINFORCED CONCRETE PIPE, CLASS III POLYVINYL-CHLORIDE (PVC) PIPE SMOOTH BORE POLYETHYLENE - ADS OR HANCOR

2. TOPSOIL STRIPPED IN AREAS OF CONSTRUCTION THAT IS SUITABLE FOR REUSE AS LOAM SHALL BE STOCKPILED ON SITE AT A LOCATION TO BE DESIGNATED BY THE OWNER. UNSUITABLE SOIL SHALL BE SEPARATED, REMOVED AND DISPOSED OF AT AN APPROVED DISPOSAL LOCATION OFF SITE.

3. THE CONTRACTOR SHALL ANTICIPATE THAT GROUNDWATER WILL BE ENCOUNTERED DURING CONSTRUCTION AND SHALL INCLUDE SUFFICIENT COSTS WITHIN THEIR BID TO PROVIDE DEWATERING AS NECESSARY. NO SEPARATE PAYMENT SHALL BE MADE TO THE CONTRACTOR FOR DEWATERING.

EROSION CONTROL NOTES

LAND DISTURBING ACTIVITIES SHALL BE ACCOMPLISHED IN A MANNER AND SEQUENCE THAT CAUSES THE LEAST PRACTICAL DISTURBANCE OF THE

PRIOR TO BEGINNING ANY CLEARING/LAND DISTURBING ACTIVITIES, THE CONTRACTOR SHALL INSTALL THE PERIMETER SILT FENCES AND THE CONSTRUCTION ENTRANCE.

ALL GROUND AREAS DISTURBED FOR CONSTRUCTION WILL BE GRADED, LOAMED AND SEEDED AS SOON AS POSSIBLE. PERMANENT SEED MIXTURE SHALL CONFORM TO THE SEEDING PLAN CONTAINED IN THE EROSION CONTROL NOTES INCLUDED ON SHEET C113.

PRIOR TO PAVING, THE CONTRACTOR SHALL FLUSH SEDIMENT FROM ALL STORM DRAIN LINES. REMOVE ACCUMULATED SEDIMENT FROM SUMPS AND INVERTS AND PROPERLY DISPOSE OF.

ALL CATCH BASINS WITH OUTLET PIPES 18" DIAMETER OR LESS SHALL BE PROVIDED WITH A "SNOUT" SEDIMENTATION HOOD PER DETAIL.

SILT FENCES SHALL BE INSPECTED, REPAIRED AND CLEANED AS

NOTED IN THE EROSION CONTROL NOTES. 7. THE CONTRACTOR SHALL REPAIR AND ADD STONE TO THE

CONSTRUCTION ENTRANCE AS IT BECOMES SATURATED WITH MUD TO

SILT REMOVED FROM AROUND INLETS AND BEHIND THE SILT FENCES SHALL BE PLACED ON A TOPSOIL STOCKPILE AND MIXED INTO IT FOR LATER USE IN LANDSCAPING OPERATIONS.

EROSION CONTROL NOTES ACCOMPANY THIS PLAN SET AND ARE CONTAINED ON DRAWING C113 OF THIS PLAN SET.

THE MAINTENANCE SCHEDULE FOR THE CATCH BASIN SEDIMENT SUMPS IS CONTAINED IN THE EROSION CONTROL NOTES INCLUDED ON

11. THE CONTRACTOR IS CAUTIONED THAT FAILURE TO COMPLY WITH THE SEQUENCE OF CONSTRUCTION, EROSION/SEDIMENT CONTROL PLAN, AND OTHER PERMIT REQUIREMENTS BASED UPON ANY THIRD PARTY REVIEW (ie MAINEDEP) MAY RESULT IN MONETARY PENALTIES. THE CONTRACTOR SHALL BE ASSESSED ALL SUCH PENALTIES AT NO COST TO THE OWNER OR

12. ALL NON-PAVED AREAS DISTURBED DURING CONSTRUCTION SHALL BE LOAMED AND SEEDED, UNLESS OTHERWISE SHOWN ON THE PLANS OR DIRECTED BY THE OWNER.

13. ALL DISTURBED AREAS ARE TO RECEIVE A MINIMUM OF 4" OF TOPSOIL PRIOR TO PERMANENT SEEDING UNLESS OTHERWISE SHOWN ON THE PLANS.

UTILITIES

BATH WATER DISTRICT 1 LAMBARD STREET BATH, ME 04530 (207) 443-2391 CONTACT: NATHAN BODGE

SEWER:

BATH PUBLIC WORKS 450 OAK GROVE BATH, ME 04530 (207) 443-8357 CONTACT: CHRIS WALLACE

BRUNSWICK REGION

ELECTRIC:

(207) 242-3515CONTACT: GARY HAM TELEPHONE:

CONSOLIDATED COMMUNICATIONS 5 DAVIS FARM ROAD PORTLAND, MAINE 04103 CONTACT: PATRICK MORRISON

TIME WARNER CABLE/SPECTRUM 115 JOHNSON ROAD PORTLAND, MAINE 04102 207.253.2324 CONTACT: MARK PELLETIER

MAINE NATURAL GAS 9 INDUSTRIAL PARKWAY BRUNSWICK, ME 04011 (207) 729-0420 CONTACT: JOSEPH GAUTHIER

INDEX

LOCATION MAP

N.T.S.

COO1 — Cover Sheet, General Notes, and Legend

PROJECT LOCATION

C101 — Existing Conditions Plan (1 of 3)

C102 — Existing Conditions Plan (2 of 3)

C103 — Existing Conditions Plan (3 of 3) C104 — Demolition Plan

C105 - Site Plan

C106 - Grading, Drainage, and Erosion Control Plan

C107 - Utility Plan

C108 — Stormwater Management Plan

C109 - Site Details

C110 - Utility Details

C111 — Drainage Details

C112 — Erosion Details

C113 — Erosion Control Notes

CALL BEFORE YOU DIG **|-888-344-7233**

PERMITS

TYPE OF PERMIT

STORMWATER MANAGEMENT LAW

SITE PLAN APPLICATION

GOVERNING BODY

MAINE DEPARTMENT OF ENVIRONMENTAL PROTECTION 312 CANCO ROAD PORTLAND, ME 04103 (207) 822-6300

CITY OF BATH


CONTACT: ALISON SIROIS APPROVED:

PLANNING AND DEVELOPMENT (CITY PLANNING OFFICE) 55 FRONT STREET BATH, ME 04530 (207) 443-8363 CONTACT: JENNIFER CURTIS

<u>STATUS</u>

APPROVED:

NOTE: THIS PLAN SET IS ISSUED FOR PERMITTING PURPOSES AND SHALL NOT BE USED FOR CONSTRUCTION.



JOB J				
_				
-SRV				
Ĥ				
OR.A				
ST(
//GF	Rev.	Date	Revision	
-	•			_

PERMITTING	4/4/25	RJB
Issued For	Date	Ву


		Design: TAL	Draft: GJH	Date: APRIL 2025
1		Checked: RJB	Scale: NTS	Job No.: 4319
1		File Name: 4319—0	COVER.dwg	
1		This plan shall	not be modified	without written
		permission from	Gorrill Palmer.	Any
	RJB	alterations, auth at the user's so	norized or otner	wise, snail be
	Rν	Corrill Dalmor	ole lisk ullu witi	lout hability to




Gorrill Palmer, an LIB Engineering Company GorrillPalmer.com (207) 772-2515 300 Southborough Drive - Suite 200 South Portland, ME 04106

Cover Sheet, General Notes, and Legend Bath Fire Headquarters 826 High Street, Bath, ME 04530 Context Architecture 65 Franklin Street, Boston , MA 02110








	THE LEWIS TO SERVICE	LYPIE OF MAIN	BRIAN R	STODDARD /	TAN SESS NY	 PON FESSION OF	SURVE
_							<u>8</u> 0

Thumand .						
		DATA		ION FROM SEBAGO TECHNICS, INC. ANY ALTERATIONS, SK AND WITHOUT LIABILITY TO SEBAGO TECHNICS. INC.		

DESIGNED	-]			
DRAWN	CNG			
CHECKED	BRS			
DATE	07/26/2024			
SCALE	1" = 20'			
PROJECT	240280			

SHEET 1 OF 3










					REV: BY: DATE: STATUS:	THIS PLAN SHALL NOT BE MODIFIED WITH	AUTHORIZED OR OTHERWISE, SHALL BE.
	つしてい	H E C H N - C S	SEBAGOTECHNICS.COM	75 John Roberts Rd. Suite 4A	South Portland, ME 04106		South Portland, Bridgton, Sanford and Bath


STATION HEADQUARTERS I STREET, 16 MAPLE STREE XISTING CONDITIONS PLAN

1 R T 28	8 5 O 8 8				
ESIGNED	-				
DRAWN	CNG				
HECKED	BRS				
DATE	07/26/2024				
SCALE	1" = 20'				
PROJECT	240280				

SHEET 2 OF 3









THE OF A	ALAY S	STODDARD	TAN BCAC / 1/2	The Control of the Co	TAN LESSION TO	SURVENIN
\prod						ATIONS, CS. INC.


					REV: BY: DATE: STATUS:	THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSIC	AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK	
	りてい	В С Н С В	SEBAGOTECHNICS.COM	75 John Roberts Rd. Suite 4A	South Portland, ME 04106 207-200-2100		uth Portland, Bridgton, Sanford and Bath	


S=B/	T E C H	SEBAGOTECHI 75 John Roberts F South Portland, I 207-200-2	South Portland, Bridgton

9 6 正 8	85088
	=
ESIGNED	-
DRAWN	CNG
HECKED	BRS
DATE	07/26/2024
SCALE	1" = 20'
PROJECT	240280

SHEET 3 OF 3

(IN FEET) 1 INCH = 20 FT.






Date


Issued For


Date


Revision


C105













HEAVY DUTY R-TANK
NOT TO SCALE

STORMWATER MANAGMENT PLAN
1"=30'



NOTE: THIS PLAN SET IS ISSUED FOR PERMITTING PURPOSES AND SHALL NOT BE USED FOR CONSTRUCTION.



9				
<				
-SR				
ė				
ORA				
				PERMIT
/GP	Rev.	Date	Revision	Issu

PERMITTING	4/4/25	RJB
Issued For	Date	Ву


	Desig	ın: TAL		Draf	t:	GJH		Date: APF	≀IL 20
	Chec	ked: F	RJB	Scal	e:	1"=30'		Job No.:	4319
	File	Name:	4319-	WQ.dv	vg				
	This	plan	shall	not	be	modif	ied	without	writ


This plan shall not be modified without writter permission from Gorrill Palmer. Any alterations, authorized or otherwise, shall be at the user's sole risk and without liability to Gorrill Palmer.




Gorrill Palmer, an LJB Engineering Company	
GorrillPalmer.com	
(207) 772-2515	
300 Southborough Drive - Suite 200	
South Portland, ME 04106	


Drawing Name:	Stormwater Management Plan	abla
Project:	Bath Fire Headquarters 826 High Street, Bath, ME 04530	
Client:	Context Architecture 65 Franklin Street, Boston , MA 02110	








NOT TO SCALE





WHITE REFLECTIVE TRAFFIC PAINT

STOP BAR


STOP BAR

NOTE:
ALL TRAFFIC MARKINGS TO BE SOLID WHITE REFLECTIVE TRAFFIC PAINT AS PER DIMENSIONS BELOW.

GUARD POST

NOT TO SCALE


PAVEMENT MARKINGS



NOTES

APPLY TACK COAT BETWEEN BINDER AND SURFACE COURSES.
 ALL MATERIALS SHALL CONFORM TO MDOT SPECIFICATIONS, LATEST REVISION.


STANDARD DUTY BITUMINOUS CONCRETE PAVEMENT SECTION NOT TO SCALE




TYPICAL PAVEMENT SECTION

NEW PAVEMENT ADJACENT TO EXISTING PAVEMENT


2. ALL MATERIALS SHALL CONFORM TO MDOT SPECIFICATIONS, LATEST REVISION.



CONCRETE PAD FOR GENERATOR DETAIL NOT TO SCALE




BARRIER FREE RAMP DETAIL




TYPE 3A CURB DETAIL

NOT TO SCALE




SIDEWALK




TIPDOWN CURB

NOT TO SCALE




PARKING SPACE DIMENSIONS



NOTE: VERTICAL GRANITE CURB SHALL MEET THE REQUIREMENTS OF SECTION 609 OF THE MAINE DEPARTMENT OF TRANSPORTATION (MAINEDOT) STANDARD SPECIFICATIONS, LATEST REVISION, AND THE DIMENSIONS SHOWN ON THE DRAWINGS. SLOPED GRANITE CURB SHALL MEET THE REQUIREMENTS OF SECTION 609 OF THE STANDARD SPECIFICATIONS, LATEST REVISION, AND THE DIMENSIONS SHOWN ON THE DRAWINGS.

VERTICAL GRANITE CURB

NOTE: THIS PLAN SET IS ISSUED FOR PERMITTING PURPOSES AND SHALL NOT BE USED FOR CONSTRUCTION.



JOB			
< I			
-SRV			
ĠĖ			
2R∕			
)ST			
\\GPSTORA(Rev.	Date	Revision

PERMITTING	4/4/25	RJB
Issued For	Date	Ву

	_		-				
		Design: TAL	Draft:	GJH	Date: APRIL 2025		
		Checked: RJB	Scale:	NTS	Job No.: 4319		
		File Name: 4319-DETAILS.dwg					
	This plan shall not be modified without written						
	permission from Gorrill Palmer. Any alterations, authorized or otherwise, shall be						
3					wise, shall be nout liability to		
		∎at tne users s	oie risk	c and with	nout Hability to $lacktrel{I}$		

Gorrill Palmer.




Gorrill Palmer, an LJB Engineering Company GorrillPalmer.com (207) 772-2515	
300 Southborough Drive - Suite 200 South Portland, ME 04106	ľ

Drawing Name:	Site Details
Project:	Bath Fire Headquarters 826 High Street, Bath, ME 04530
Client:	Context Architecture 65 Franklin Street, Boston , MA 02110

Drawing No.


C109




THRUST/RETAINER GLAND SCHEDULE 1/4 BEND 90° USE POURED IN-PLACE THRUST BLOCK WITH RETAINERS 1/8 BEND 45° THRUST BLOCK WITH RETAINERS 1/16 BEND 22 1/2° THRUST BLOCK 1/32 BEND 11 1/4° THRUST BLOCK


THE ABOVE SCHEDULE IS SUBJECT TO THE APPROVAL OF THE ON-SITE INSPECTOR DUE TO SOILS AND WORKING PRESSURES IN THE AREA.

THRUST BLOCK PLACEMENT ON BENDS





WATER SERVICE NOT TO SCALE



WATER SERVICE TRENCH SECTION


1. THE BEARING SURFACE OF THE THRUST BLOCK SHALL BE THE SURFACE AREA OF THE THRUST BLOCK WHICH IS CAST AGAINST THE TRENCH WALL. THE BEARING SURFACE SHALL NOT EXCEED THE FOLLOWING LOADINGS:

IN-SITU CONDITION	<u>ALLOWABLE</u>
BEDROCK	3,000 psf
SAND OR OUTWASH DEPOSITS	1,500 psf
OTHER SOILS	1,000 psf
E THRUST SHALL BE COMPUTED ON THE CROSS SECTIONAL AREA OF TH THRUST BLOCK FOR A 1/4 BEND O ARING AGAINST CLAY WOULD REQU 7.5 s.f.	HE PIPE. FOR EXAMPLE, ON AN 8" WATER MAIN


2. INSTALL POLY BARRIER BETWEEN PIPE AND ALL THRUST

3. ANY WORK RELATED TO WATER PIPING OR DETAILS SHALL BE IN ACCORDANCE WITH THE BATH WATER AND SEWER DISTRICT SPECIFICATIONS.

THRUST BLOCK NOTES



STANDARD TEE BLOCKING NOT TO SCALE




NUMBERS ARE FOR 5.25"

TYPICAL VALVE


TYPICAL VALVE

TYPICAL VALVE BOXES NOT TO SCALE



NOTE: ONE CONDUIT CAPPED FOR SPARE, PROVIDE GALVANIZED STEEL LONG SWEEP AT RISER POLE AND EXTEND GALVANIZED CONDUIT TO 10' ABOVE GRADE AT POLE WITH STAND-OFF BRACKETS

UTILITY TRENCH-PRIMARY ELECTRIC, TELEPHONE & COMMUNICATIONS NOT TO SCALE



SCHEDULE OF TRENCH BACKFILL		
TYPE OF PIPE	EMBEDMENT MATERIAL	SELECT BACKFILL
CMP DUCTILE IRON RCP	MDOT 703.22 TYPE B UD BACKFILL	MDOT 703.22 TYPE B UD BACKFILL
PVC-SDR 35 HDPE	MDOT 703.22 TYPE C 3/4" CRUSHED STONE	MDOT 703.22 TYPE B UD BACKFILL
PERFORATED PVC-SDR35 HDPE	MDOT 703.22 TYPE C 3/4" CRUSHED STONE	MDOT 703.22 TYPE C 3/4" CRUSHED STONE

NOTE:

1. BRACING AND SHEETING OR OTHER TRENCH PROTECTION TO BE PROVIDED TO MEET APPLICABLE STATE AND O.S.H.A. SAFETY STANDARDS. ALL SUCH TRENCH PROTECTION TO BE THE RESPONSIBILITY OF THE CONTRACTOR.

2. INSTALL WARNING TAPE DIRECTLY ABOVE UTILITIES, 12" BELOW FINISH GRADE.


MINIMUM COVER PIPE

2'-0" DRAIN (
5'-5" WATER
5'-0" SEWER

(1) COVER BETWEEN 2' AND 3' SHALL INCLUDE 4" RIGID INSULATION. COVER BETWEEN 3' AND 4' SHALL INCLUDE 2" RIGID INSULATION.


- COVER SHALL HAVE UTILITY NAME (SEWER, STORM, ETC.) CAST IN · 26"ø MH FRAME AND COVER NEENAH R-1556-A OR APPROVED EQUAL WITH MIN. 24" CLEAR OPENING FORGED ALUMINUM OR COPOLYMER - CEMENT MORTAR (TYPE II CEMENT) POLYPROPYLENE · ADJUST TO GRADE WITH SEWER BRICK SAFETY STEPS -WITH A MIN. OF 1 COURSE AND A MAX. OF 3 COURSES PRECAST CONCRETE TRUNCATED MH CONE. WHEN DEPTH OF SEWER IS LESS THAN OR EQUAL TO 5', USE FLATTOP IN LIEU OF TRUNCATED CONE. FOR JOINTS OF WATERTIGHT MANHOLE KENT SEAL, RAM NEK OR "O" RING MUST MEET AASHTO M198B - ALL PRECAST CONC. SECTIONS SHALL CONFORM TO ASTM C478 AND BE DESIGNED FOR H-20 LOADING MAX. PRECAST CONC. BASE SECTION WITH PIPE OPENINGS AS APPROVED BY THE ENGINEER SIDEWALL OF MANHOLE TO BE BACKFILLED WITH MDOT 703.22 TYPE B UNDERDRAIN EXTERIOR OF MANHOLE SHALL BE TREATED WITH 2 COATS OF THE FOLLOWING: • TREMCO 112 FOUNDATION COATING • CS55 BY GAGNE PRECAST FLEXIBLE SLEEVE CAST • MINWAX FIBOROUS BRUSH COAT IN PRECAST SECTION TO BE INTERPACE, LOCK - BRICK CHANNEL TO BE AASHTO M-91-42 GRADE SA SEWER BRICK JOINT OR EQUAL-- 12" THICK 3/4" CRUSHED STONE BASE

4'-0" PRECAST SEWER MANHOLE AND DRAIN MANHOLE



SANITARY SEWER MANHOLE BRICK CHANNEL INSTALLATION


© OF PIPE AND TRENCH



SECONDARY ELECTRICAL TRENCH DETAIL

NOTE: THIS PLAN SET IS ISSUED FOR PERMITTING PURPOSES AND SHALL

NOT BE USED FOR CONSTRUCTION.



- 1			
JOB,			
_			
-SR			
Ĥ			
OR.A			
GPSTORAGE			
//GP	Rev.	Date	Revision
•			

_			
I			
	PERMITTING	4/4/25	RJB
	Issued For	4/4/25 Date	Ву
_			

		Design: TAL Draft: GJH Date: APRIL 2025
		Checked: RJB Scale: NTS Job No.: 4319
		File Name: 4319-DETAILS.dwg
		This plan shall not be modified without written
		permission from Gorrill Palmer. Any
4/4/25	RJB	alterations, authorized or otherwise, shall be
Data	D	at the user's sole risk and without liability to


Gorrill Palmer.




Gorrill Palmer, an LJB Engineering Company GorrillPalmer.com (207) 772-2515 300 Southborough Drive - Suite 200 South Portland, ME 04106

Drawing Name:	Utility Details	
Project:	Bath Fire Headquarters 826 High Street, Bath, ME 04530	
Client:	Context Architecture 65 Franklin Street, Boston , MA 02110	

Drawing No.







- 1. CONCRETE MINIMUM COMPRESSIVE STRENGTH 4,000 PSI @ 28 DAYS WITH STEEL REINFORCEMENT.
- 2. AS PER CENTRAL MAINE POWER COMPANY SPECIFICATIONS.
- 3. ONE 8" x 24" KNOCKOUT PROVIDED EACH WALL.
- 4. FOR 750 5000 KVA THREE PHASE TRANSFORMER.
- 5. FINISH GRADE SHALL BE GRADED TO ALLOW SURFACE WATER TO FLOW AWAY FROM THE PAD.

9'-0" TRANSFORMER PAD

NOT TO SCALE



4' WIDE PEDESTRIAN SINGLE SWING GATE (WHERE SHOWN ON PLANS)




INTERMEDIARY LINE POST DETAIL

TERMINAL, CORNER & GATE POST DETAIL

CHAIN LINK FENCE INSTALLATION SCHEDULE				
FENCE HEIGHT (A)	TOP RAIL PIPE DIA. (B)	LINE POST PIPE DIA. (C)	CORNER, TERMINAL OF GATE POST PIPE DIA (D)	
4'	1.66"	1.90"	2.375"	
6'	1.66"	1.90"	2.375"	
8'	1.66"	2.375"	2.875"	
10'	1.66"	2.875"	2.875"	

	SWINGING GATE TION SCHEDULE
FENCE HEIGHT (A)	GATE POST PIPE DIA. (B)
4'	2.875"
6'	2.875"
8'	4.000"
10'	4.000"




NOTES:

1. DIMENSIONS FOR PIPE DIAMETERS ARE NOMINAL OUTSIDE DIAMETERS. 2. REFER TO PLANS FOR LOCATION & HEIGHT OF FENCES TO BE INSTALLED.

GALVANIZED CHAIN LINK FENCE DETAILS

NOT TO SCALE



NOTE: FOR USE ON CATCH BASIN OUTLET 18" IN DIAMETER AND LESS

NOTE: THIS PLAN SET IS ISSUED FOR PERMITTING PURPOSES AND SHALL NOT BE USED FOR CONSTRUCTION.

SRV 		
AGE-		
STORAGE		
Rev	. Date	Revision

PERMITTING	4/4/25	RJB
Issued For	4/4/25 Date	Ву


	Design: IAL	Draft:	GJH	Date: APRIL 2025
	Checked: RJB	Scale:	NTS	Job No.: 4319
	File Name: 4319—[ETAILS.d	wg	
	This plan shall permission from alterations, authors	ı Gorril norized	l Palmer. or other	Any wise, shall be
/	at the user's so Gorrill Palmer.	ole risk	c ana witr	nout liability to




Gorrill Palmer, an LJB Engineering Company GorrillPalmer.com (207) 772-2515 300 Southborough Drive - Suite 200 South Portland, ME 04106


Drawing Name:	Drainage Details	
Project:	Bath Fire Headquarters 826 High Street, Bath, ME 04530	
Client:	Context Architecture 65 Franklin Street, Boston , MA 02110	






CATCH BASIN INLET FILTER NOT TO SCALE







STABILIZED CONSTRUCTION ENTRANCE NOT TO SCALE



SILTATION FENCE






SPECIFIC APPLICATION

THIS METHOD OF INLET PROTECTION IS APPLICABLE WHERE HEAVY FLOWS ARE EXPECTED AND WHERE AN OVERFLOW CAPACITY IS NECESSARY TO PREVENT EXCESSIVE PONDING AROUND THE STRUCTURE.

- NOTES:
- 1. PLACE CONCRETE BLOCKS LENGTHWISE ON THEIR SIDES IN A SINGLE ROW AROUND THE PERIMETER OF THE INLET, WITH THE ENDS OF ADJACENT BLOCKS ABUTTING. THE HEIGHT OF THE BARRIER CAN BE VARIED, DEPENDING ON DESIGN NEEDS, BY STACKING COMBINATIONS OF 4", 8" AND 12" WIDE BLOCKS. THE BARRIER OF BLOCKS SHALL BE AT LEAST 12 INCHES HIGH, AND NO GREATER THAN 24" HIGH.
- 2. WIRE MESH SHALL BE PLACED OVER THE OUTSIDE VERTICAL FACE (WEBBING) OF THE CONCRETE BLOCKS TO PREVENT STONE FROM BEING WASHED THROUGH THE HOLES IN THE BLOCKS. HARDWARE CLOTH OR COMPARABLE WIRE MESH WITH 1/2" OPENINGS SHALL BE USED.
- 3. STONE SHALL BE PILED AGAINST THE WIRE TO THE TOP OF THE BLOCK BARRIER, AS SHOWN IN DETAIL. THE STONE FILTER SHALL BE 3/4" CRUSHED STONE.
- 4. IF THE STONE FILTER BECOMES CLOGGED WITH SEDIMENT, SO THAT IT NO LONGER ADEQUATELY PERFORMS ITS FUNCTION, THE STONE MUST BE PULLED AWAY FROM THE BLOCKS, CLEANED AND REPLACED.

STONE SEDIMENT BARRIER

NOT TO SCALE



SPACING BETWEEN CHECK DAMS

So L (FT./FT.) (FT.)

0.020 75
0.030 50
0.040 40
0.050 30
0.080 20
0.100 10

STONE CHECK DAM


NOTES:

- 1. THE WOOD WASTE COMPOST/BARK MIX SHALL CONFORM TO THE FOLLOWING STANDARDS:
- A. MOISTURE CONTENT 30-60%. B. pH - 5.0 - 8.0.
- C. SCREEN SIZE 100% LESS THAN 3", MAX. 70% LESS THAN 1".

 D. NO LESS THAN 40% ORGANIC MATERIAL (DRY WEIGHT) BY LOSS OF IGNITION.
- E. NO STONES LARGER THAN 2" IN DIAMETER.
 F. SILTS, CLAYS OR SUGAR SANDS ARE NOT ACCEPTABLE IN THE MIX.
- 2. THE COMPOST BERM SHALL BE PLACED, UNCOMPACTED, ALONG A RELATIVELY LEVEL CONTOUR.
- 3. THE WOOD WASTE COMPOST/BARK FILTER BERM MAY BE USED IN LIEU OF SILTATION FENCE, AT THE TOE OF SHALLOW SLOPES, ON FROZEN GROUND, LEDGE OUT CROPS, VERY ROOTED FORESTED AREA OR AT THE EDGE OF GRAVEL PARKING AREAS.


4. BERMS SHALL REMAIN IN PLACE UNTIL UPSTREAM AREA IS COMPLETED OR 70% CATCH OF VEGETATION IS ATTAINED. BERMS SHALL BE REMOVED BY SPREADING SUCH THAT NATIVE EARTH CAN BE SEEN BELOW.

5. WOODWASTE COMPOST BARK FILTER SHALL NOT BE USED IN WETLAND AREAS.



WOOD WASTE COMPOST/BARK FILTER BERM DETAIL NOT TO SCALE

NOTE: THIS PLAN SET IS ISSUED FOR PERMITTING PURPOSES AND SHALL NOT BE USED FOR CONSTRUCTION.



JOB			
Ś			
-SR			
ĠĖ			
ORAGE			
/\GF	Rev.	Date	Revision

PERMITTING	4/4/25	RJB
Issued For	Date	Ву


	Design: TAL	Draft: GJH	Date: APRIL 2025
	Checked: RJB	Scale: NTS	Job No.: 4319
	File Name: 4319-D	ETAILS.dwg	
	This plan shall permission from	Gorrill Palmer.	Any
RJB	alterations, auth	norized or other	wise, snall be
7	Tar the user's so	ole lisk and with	Tout hability to

Gorrill Palmer.



Gorrill Palmer, an LJB Engineering Company GorrillPalmer.com (207) 772-2515 300 Southborough Drive - Suite 200 South Portland, ME 04106

Drawing Name:	Erosion Control Details
Project:	Bath Fire Headquarters 826 High Street, Bath, ME 04530
Client:	Context Architecture 65 Franklin Street, Boston , MA 02110



DEVELOPMENT OF A CAREFUL CONSTRUCTION SEQUENCE.

RAPID REVEGETATION OF DENUDED AREAS TO MINIMIZE THE PERIOD OF SOIL EXPOSURE. RAPID STABILIZATION OF DRAINAGE PATHS TO AVOID RILL AND GULLY EROSION.

THE USE OF ON-SITE MEASURES TO CAPTURE SEDIMENT (HAY BALES/ STONE CHECK DAMS/SILT FENCE, ETC.)

THE FOLLOWING TEMPORARY AND PERMANENT EROSION AND SEDIMENT CONTROL DEVICES WILL BE IMPLEMENTED AS PART OF THE SITE DEVELOPMENT. THESE DEVICES SHALL BE INSTALLED AS INDICATED ON THE PLANS OR AS DESCRIBED WITHIN THIS REPORT. FOR FURTHER REFERENCE, SEE THE LATEST EDITION OF THE MAINE EROSION AND SEDIMENT CONTROL PRACTICES FIELD GUIDE FOR

WATER FROM CONSTRUCTION TRENCH DEWATERING SHALL PASS FIRST THROUGH A FILTER BAG OR SECONDARY CONTAINMENT STRUCTURE (E.G. HAY BALE LINED POOL) PRIOR TO DISCHARGE. THE DISCHARGE SITE SHALL BE SELECTED TO AVOID FLOODING, ICING, AND SEDIMENT DISCHARGES TO A PROTECTED RESOURCE. IN NO CASE SHALL THE FILTER BAG OR CONTAINMENT STRUCTURE BE LOCATED WITHIN 50 FEET OF A PROTECTED NATURAL RESOURCE. DEWATERING DISCHARGE SHALL NOT BE DIRECTED ACROSS ADJACENT PROPERTIES IN A CONCENTRATED MANNER.

B. INSPECTION AND MONITORING

MAINTENANCE MEASURES SHALL BE APPLIED AS NEEDED DURING THE ENTIRE CONSTRUCTION SEASON. AFTER EACH RAINFALL, SNOW STORM OR PERIOD OF THAWING AND RUNOFF, THE SITE CONTRACTOR SHALL PERFORM A VISUAL INSPECTION OF ALL INSTALLED EROSION CONTROL MEASURES AND PERFORM REPAIRS AS NEEDED TO INSURE THEIR CONTINUOUS FUNCTION. FOLLOWING THE TEMPORARY AND/OR FINAL SEEDING AND MULCHING, THE CONTRACTOR SHALL IN THE SPRING INSPECT AND REPAIR ANY DAMAGES AND/OR UNESTABLISHED SPOTS. ESTABLISHED VEGETATIVE COVER MEANS A MINIMUM OF 90% OF AREAS VEGETATED WITH VIGOROUS GROWTH.

THE FOLLOWING STANDARDS MUST BE MET DURING CONSTRUCTION.

(a) INSPECTION AND CORRECTIVE ACTION, INSPECT DISTURBED AND IMPERVIOUS AREAS, EROSION CONTROL MEASURES, MATERIALS STORAGE AREAS THAT ARE EXPOSED TO PRECIPITATION, AND LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE. INSPECT THESE AREAS AT LEAST ONCE A WEEK AS WELL AS BEFORE AND WITHIN 24 HOURS AFTER A STORM EVENT (RAINFALL), AND PRIOR TO COMPLETING PERMANENT STABILIZATION MEASURES. A PERSON WITH KNOWLEDGE OF EROSION AND STORMWATER CONTROL, INCLUDING THE STANDARDS AND CONDITIONS IN THE PERMIT, SHALL CONDUCT THE INSPECTIONS.

(b) MAINTENANCE. IF BEST MANAGEMENT PRACTICES (BMPS) NEED TO BE REPAIRED, THE REPAIR WORK SHOULD BE INITIATED UPON DISCOVERY OF THE PROBLEM BUT NO LATER THAN THE END OF THE NEXT WORKDAY. IF ADDITIONAL BMPS OR SIGNIFICANT REPAIR OF BMPS ARE NECESSARY. IMPLEMENTATION MUST BE COMPLETED WITHIN 7 CALENDAR DAYS AND PRIOR TO ANY STORM EVENT (RAINFALL). ALL MEASURES MUST BE MAINTAINED IN EFFECTIVE OPERATING CONDITION UNTIL AREAS ARE PERMANENTLY STABILIZED.

(c) DOCUMENTATION. KEEP A LOG (REPORT) SUMMARIZING THE INSPECTIONS AND ANY CORRECTIVE ACTION TAKEN. THE LOG MUST INCLUDE THE NAME(S) AND QUALIFICATIONS OF THE PERSON MAKING THE INSPECTIONS, THE DATE(S) OF THE INSPECTIONS, AND MAJOR OBSERVATIONS ABOUT THE OPERATION AND MAINTENANCE OF EROSION AND SEDIMENTATION CONTROLS, MATERIALS STORAGE AREAS, AND VEHICLES ACCESS POINTS TO THE PARCEL. MAJOR OBSERVATIONS MUST INCLUDE BMPS THAT NEED MAINTENANCE, BMPS THAT FAILED TO OPERATE AS DESIGNED OR PROVED INADEQUATE FOR A PARTICULAR LOCATION, AND LOCATION(S) WHERE ADDITIONAL BMPS ARE NEEDED. FOR EACH BMP REQUIRING MAINTENANCE, BMP NEEDING REPLACEMENT, AND LOCATION NEEDING ADDITIONAL BMPS, NOTE IN THE LOG THE CORRECTIVE ACTION TAKEN AND WHEN IT WAS TAKEN.

THE LOG MUST BE MADE ACCESSIBLE TO DEPARTMENT STAFF AND A COPY MUST BE PROVIDED UPON REQUEST. THE PERMITTEE SHALL RETAIN A COPY OF THE LOG FOR A PERIOD OF AT LEAST THREE YEARS FROM THE COMPLETION OF PERMANENT STABILIZATION.

C. TEMPORARY EROSION CONTROL MEASURES

TEMPORARY EROSION CONTROL MEASURES SHALL BE INSTALLED BY THE CONTRACTOR AS REQUIRED BY THIS REPORT AND AS SHOWN ON THE PLAN SET FOR THE PROJECT. ADDITIONAL EROSION CONTROL MEASURES SHALL BE INSTALLED IF DEEMED NECESSARY BY ON-SITE INSPECTIONS OF THE OWNER, MDEP, OR THEIR REPRESENTATIVES AT NO ADDITIONAL COST TO THE OWNER.

THE FOLLOWING MEASURES ARE PLANNED AS TEMPORARY EROSION/SEDIMENTATION CONTROL MEASURES DURING CONSTRUCTION:

1. SILTATION FENCE OR WOOD WASTE COMPOST BERMS SHALL BE INSTALLED DOWNSTREAM OF ANY DISTURBED AREAS TO TRAP RUNOFF- BORNE SEDIMENTS UNTIL GRASS AREAS ARE REVEGETATED. THE SILT FENCE AND/OR WOOD WASTE COMPOST BERMS SHALI BE INSTALLED PER THE DETAILS PROVIDED IN THIS PACKAGE AND INSPECTED AT LEAST ONCE A WEEK AND BEFORE AND IMMEDIATELY AFTER A STORM EVENT OF 0.5 INCHES OR GREATER, AND AT LEAST DAILY DURING PROLONGED RAINFALL. REPAIRS SHALL BE MADE I THERE ARE ANY SIGNS OF EROSION OR SEDIMENTATION BELOW THE FENCE OR BERM LINE. IF THERE ARE SIGNS OF UNDERCUTTING AT THE CENTER OR THE EDGES, OR IMPOUNDING OF LARGE VOLUMES OF WATER BEHIND THE FENCE OR BERM. THE BARRIER SHALL BE REPLACED WITH A STONE CHECK DAM. WOOD WASTE COMPOST BERMS ARE NOT TO BE USED ADJACENT TO WETLAND AREAS THAT ARE

2. STRAW OR HAY MULCH INCLUDING HYDROSEEDING IS INTENDED TO PROVIDE COVER FOR DENUDED OR SEEDED AREAS UNTIL REVEGETATION IS ESTABLISHED. MULCH PLACED BETWEEN APRIL 15TH AND OCTOBER 15TH ON SLOPES OF LESS THEN 15 PERCENT SHALL BE ANCHORED BY APPLYING WATER; MULCH PLACED ON SLOPES OF EQUAL TO OR STEEPER THAN 15 PERCENT SHALL BE COVERED BY A FABRIC NETTING AND ANCHORED WITH STAPLES IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATION. FABRIC NETTING AND STAPLES SHALL BE USED ON DISTURBED AREAS WITHIN 50' OF LAKES, STREAMS, AND WETLANDS REGARDLESS OF THE UPSTREAM SLOPE. MULCH PLACED BETWEEN OCTOBER 15TH AND APRIL 15TH ON SLOPES EQUAL TO OR STEEPER THAN 8 PERCENT SHALL BE COVERED WITH A FABRIC NETTING AND ANCHORED WITH STAPLES IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS. SLOPES STEEPER THAN 3:1 AND EQUAL TO OR FLATTER THAN 2:1, WHICH ARE TO BE REVEGETATED, SHALL RECEIVE CURLEX BLANKETS BY AMERICAN EXCELSIOR OR EQUAL. SLOPES STEEPER THAN 2:1 SHALL RECEIVE RIPRAP AS NOTED ON THE PLANS. THE MULCH APPLICATION RATE FOR BOTH TEMPORARY AND PERMANENT SEEDING IS 75 LBS PER 1000 SF AS IDENTIFIED IN SEEDING PLAN. MULCH SHALL NOT BE PLACED OVER SNOW.

- 3. TEMPORARY STOCKPILES OF STUMPS, GRUBBINGS, OR COMMON EXCAVATION WILL BE PROTECTED AS FOLLOWS:
- a) TEMPORARY STOCKPILES SHALL NOT BE LOCATED WITHIN 100 FEET OF ANY WETLANDS WHICH WILL NOT BE DISTURBED AND SHALL BE LOCATED AWAY FROM DRAINAGE SWALES.

b) STOCKPILES SHALL BE STABILIZED WITHIN 7 DAYS BY EITHER TEMPORARILY SEEDING THE STOCKPILE BY A HYDROSEED METHOD CONTAINING AN EMULSIFIED MULCH TACKIFIER OR BY COVERING THE STOCKPILE WITH MULCH, SUCH AS HAY, STRAW, OR EROSION

c) STOCKPILES SHALL BE SURROUNDED BY SEDIMENTATION BARRIER AT THE TIME OF FORMATION.

4. ALL DENUDED AREAS THAT ARE WITHIN 100 FEET OF AN UNDISTURBED WETLAND, WHICH HAVE BEEN ROUGH GRADED AND ARE NOT LOCATED WITHIN A BUILDING PAD, PARKING AREA, OR ACCESS DRIVE SUBBASE AREA, SHALL RECEIVE MULCH OR EROSION CONTROL MESH FABRIC WITHIN 48 HOURS OF INITIAL DISTURBANCE OF SOIL. ALL AREAS WITHIN 100 FEET OF AN UNDISTURBED WETLAND SHALL BE MULCHED PRIOR TO ANY PREDICTED RAIN EVENT REGARDLESS OF THE 48 HOUR WINDOW. IN OTHER AREAS, THE TIME PERIOD MAY

5. FOR WORK, WHICH IS CONDUCTED BETWEEN OCTOBER 15TH/ AND APRIL 15TH/ OF ANY CALENDAR YEAR, ALL DENUDED AREAS, SHALL BE COVERED WITH HAY MULCH OR EROSION CONTROL MIX, APPLIED AT TWICE THE NORMAL APPLICATION RATE AND ANCHORED WITH A FABRIC NETTING. THE TIME PERIOD FOR APPLYING MULCH SHALL BE LIMITED TO 2 DAYS FOR ALL AREAS.

MOLLISON WAY SHALL BE SWEPT TO CONTROL MUD AND DUST AS NECESSARY.

DURING GRUBBING OPERATIONS STONE CHECK DAMS SHALL BE INSTALLED AT ANY EVIDENT CONCENTRATED FLOW DISCHARGE POINTS AND AS DIRECTED ON THE EROSION CONTROL PLANS.

8. SILT FENCING WITH A MINIMUM STAKE SPACING OF 6 FEET SHALL BE USED, UNLESS THE FENCE IS SUPPORTED BY WIRE FENCE REINFORCEMENT OF MINIMUM 14 GAUGE AND WITH A MAXIMUM MESH SPACING OF 6 INCHES, IN WHICH CASE STAKES MAY BE SPACED A MAXIMUM OF 10 FEET APART. THE BOTTOM OF THE FENCE SHALL BE ANCHORED. A DOUBLE ROW OF SILT FENCE SHALL BE USED

WOOD WASTE COMPOST/BARK BERMS MAY BE USED IN LIEU OF SILTATION FENCING. BERMS SHALL BE REMOVED AND SPREAD IN A LAYER NOT TO EXCEED 3"THICK ONCE UPSTREAM AREAS ARE COMPLETED AND A 90% CATCH OF VEGETATION IS ATTAINED.

10. STORM DRAIN CATCH BASIN INLET PROTECTION SHALL BE PROVIDED THROUGH THE USE OF STONE SEDIMENT BARRIERS OR APPROVED SEDIMENT BAGS (SUCH AS SILT SACK). INSTALLATION DETAILS ARE PROVIDED IN THE PLAN SET. THE BARRIERS SHALL BE INSPECTED AFTER EACH RAINFALL AND REPAIRS MADE AS NECESSARY. SEDIMENT SHALL BE REMOVED AND THE BARRIER RESTORED TO ITS ORIGINAL DIMENSIONS WHEN THE SEDIMENT HAS ACCUMULATED TO ½ THE DESIGN DEPTH OF THE BARRIER. THE BARRIER SHALL BE REMOVED WHEN THE TRIBUTARY DRAINAGE AREA HAS BEEN STABILIZED.

11. WATER AND/OR CALCIUM CHLORIDE SHALL BE FURNISHED AND APPLIED IN ACCORDANCE WITH MDOT SPECIFICATIONS — SECTION 637 - DUST CONTROL.

12. LOAM AND SEED IS INTENDED TO SERVE AS THE PRIMARY PERMANENT REVEGETATIVE MEASURE FOR ALL DENUDED AREAS NOT PROVIDED WITH OTHER EROSION CONTROL MEASURES, SUCH AS RIPRAP. APPLICATION RATES ARE PROVIDED IN THE SEEDING PLAN. SEEDING SHALL NOT OCCUR OVER SNOW.

D. PERMANENT EROSION CONTROL MEASURES

THE FOLLOWING PERMANENT EROSION CONTROL MEASURES HAVE BEEN DESIGNED AS PART OF THE EROSION/SEDIMENTATION CONTROL

ALL AREAS DISTURBED DURING CONSTRUCTION, BUT NOT SUBJECT TO OTHER RESTORATION (PAVING, RIPRAP, ETC.) WILL BE LOAMED, LIMED, FERTILIZED, MULCHED, AND SEEDED. FABRIC NETTING, ANCHORED WITH STAPLES, SHALL BE PLACED OVER THE MULCH IN AREAS AS NOTED IN TEMPORARY EROSION CONTROL MEASURES PARAGRAPH 3 OF THIS REPORT. ALL AREAS WITHIN 100 FEET OF AN UNDISTURBED WETLAND SHALL BE MULCHED PRIOR TO ANY PREDICTED RAIN EVENT REGARDLESS OF THE 48 HOUR WINDOW. NATIVE TOPSOIL SHALL BE STOCKPILED AND REUSED FOR FINAL RESTORATION WHEN IT IS OF SUFFICIENT QUALITY.

ALL STORM DRAIN PIPE OUTLETS SHALL HAVE RIPRAP APRONS AT THEIR OUTLET TO PROTECT THE OUTLET AND RECEIVING CHANNEL FROM SCOUR AND DETERIORATION. INSTALLATION DETAILS ARE PROVIDED IN THE PLAN SET. THE APRONS SHALL BE INSTALLED AND STABILIZED TO THE EXTENT PRACTICABLE PRIOR TO DIRECTING RUNOFF TO THE TRIBUTARY PIPE OR CULVERT. 1.4 IMPLEMENTATION SCHEDULE

THE FOLLOWING CONSTRUCTION SEQUENCE SHALL BE REQUIRED TO ENSURE THE EFFECTIVENESS OF THE EROSION AND SEDIMENTATION CONTROL MEASURES ARE OPTIMIZED:

IT IS ANTICIPATED THAT CONSTRUCTION OF THE FIRE STATION, ROADWAY, AND RELATED INFRASTRUCTURE WILL COMMENCE IN FALL OF 2025 AND BE COMPLETED BY FALL OF 2026.

FOR ALL GRADING ACTIVITIES, THE CONTRACTOR SHALL EXERCISE EXTREME CAUTION NOT TO OVEREXPOSE THE SITE, THIS SHALL BE ACCOMPLISHED BY LIMITING THE DISTURBED AREA.

INSTALL STABILIZED CONSTRUCTION ENTRANCE AT THE EXISTING ACCESS DRIVE OR AT THE INTERSECTION WITH MOLLISON WAY AS APPLICABLE TO PREVENT TRACKING OF SOIL ONTO THE PAVED SURFACE.

- 2. INSTALL PERIMETER SILT FENCE AND/OR WOOD WASTE BERMS PRIOR TO GRUBBING RESPECTIVE AREAS.
- CLEAR AND GRUB SITE. INSTALL STONE CHECK DAMS AT ANY EVIDENT CONCENTRATED FLOW DISCHARGE POINTS.
- 4. FOUNDATION PREPARATION AREA SHALL BE EXCAVATED FOR INSTALLATION OF THE BUILDING FOOTINGS. BUILDING WORK WILL BE ONGOING THROUGH THE REMAINDER OF THE PROJECT.
- 5. COMMENCE INSTALLATION OF DRAINAGE APPURTENANCES.
- 6. COMMENCE INSTALLATION OF WATER AND SEWER LINES.
- COMMENCE EARTHWORK AND GRADING TO SUBGRADE AS NECESSARY FOR CONSTRUCTION.
- 8. COMPLETE INSTALLATION OF UNDERGROUND UTILITIES TO WITHIN 5' OF THE BUILDINGS.
- 9. INSTALL LIGHT POLE FOUNDATIONS AND LIGHT POLES.
- 10. COMPLETE REMAINING EARTHWORK OPERATIONS.
- 11. COMPLETE INSTALLATION OF CATCH BASINS AND APPURTENANCES.
- 12. INSTALL SUB-BASE AND BASE GRAVEL WITHIN PARKING FIELDS, WALKWAYS, AND DRIVEWAYS.
- 13. INSTALL CURBING AS NEEDED.
- 14. INSTALL BASE COURSE PAVING AS WELL AS CONCRETE SURFACES.
- 15. LOAM, LIME, FERTILIZE, SEED AND MULCH DISTURBED AREAS AND COMPLETE ALL LANDSCAPING.

16. INSTALL SURFACE COURSE PAVING. STRIPE PER PLAN.

17. ONCE THE SITE IS STABILIZED AND A 90% CATCH OF VEGETATION HAS BEEN OBTAINED, REMOVE ALL TEMPORARY EROSION CONTROL

18. TOUCH UP LOAM AND SEED.

NOTE: ALL DENUDED AREAS NOT SUBJECT TO FINAL PAVING, RIPRAP, OR GRAVEL SHALL BE REVEGETATED.

PRIOR TO CONSTRUCTION OF THE PROJECT, THE CONTRACTOR SHALL SUBMIT TO THE OWNER A SCHEDULE FOR THE COMPLETION OF THE WORK, WHICH WILL SATISFY THE FOLLOWING CRITERIA:

THE ABOVE CONSTRUCTION SEQUENCE SHOULD GENERALLY BE COMPLETED IN THE SPECIFIED ORDER; HOWEVER, SEVERAL SEPARATE ITEMS MAY BE CONSTRUCTED SIMULTANEOUSLY. WORK MUST ALSO BE SCHEDULED OR PHASED TO REDUCE THE EXTENT OF THE EXPOSED AREAS AS SPECIFIED BELOW. THE INTENT OF THIS SEQUENCE IS TO PROVIDE FOR EROSION CONTROL AND TO HAVE STRUCTURAL MEASURES SUCH AS SILT FENCE AND CONSTRUCTION ENTRANCES IN PLACE BEFORE LARGE AREAS OF LAND ARE DENUDED.

- 2. THE WORK SHALL BE CONDUCTED IN SECTIONS WHICH SHALL:
- a) LIMIT THE AMOUNT OF EXPOSED AREA TO THOSE AREAS IN WHICH WORK IS EXPECTED TO BE UNDERTAKEN DURING THE PROCEEDING 30

REVEGETATE DISTURBED AREAS AS RAPIDLY AS POSSIBLE. ALL AREAS SHALL BE PERMANENTLY STABILIZED WITHIN 7 DAYS OF FINAL GRADING OR BEFORE A STORM EVENT; OR TEMPORARILY STABILIZED WITHIN 48 HOURS OF INITIAL DISTURBANCE OF SOIL FOR AREAS WITHIN 100 FEET OF AN UNDISTURBED WETLAND AND 7 DAYS FOR ALL OTHER AREAS. AREAS WITHIN 100 FEET OF AN UNDISTURBED WETLAND SHALL BE MULCHED PRIOR TO ANY PREDICTED RAIN EVENT REGARDLESS OF THE 48 HOUR WINDOW.

INCORPORATE PLANNED INLETS AND DRAINAGE SYSTEM AS EARLY AS POSSIBLE INTO THE CONSTRUCTION PHASE. THE DITCHES SHALL BÉ IMMEDIATELY LINED OR REVEGETATED AS SOON AS THEIR INSTALLATION IS COMPLETE.

- 1.5 EROSION, SEDIMENTATION AND STABILIZATION CONTROL PLAN
- THE EROSION CONTROL PLAN IS INCLUDED IN THE PLAN SET.
- 1.6 DETAILS AND SPECIFICATIONS
- THE EROSION CONTROL DETAILS AND SPECIFICATIONS ARE INCLUDED IN THE PLAN SET.

(EVEN COVERED WITH HAY OR STRAW) WITHIN 100 FEET FROM ANY NATURAL RESOURCES.

1.7 WINTER STABILIZATION PLAN

THE WINTER CONSTRUCTION PERIOD IS FROM NOVEMBER 1 THROUGH APRIL 15. IF THE CONSTRUCTION SITE IS NOT STABILIZED WITH PAVEMENT, A ROAD GRAVEL BASE, 75% MATURE VEGETATION COVER OR RIPRAP BY NOVEMBER 15 THEN THE SITE NEEDS TO BE PROTECTED WITH OVER-WINTER STABILIZATION. AN AREA CONSIDERED OPEN IS ANY AREA NOT STABILIZED WITH PAVEMENT; VEGETATION, MULCHING, EROSION CONTROL MATS, RIPRAP OR GRAVEL BASE ON A ROAD

CONTRACTOR. LIMIT THE EXPOSED AREA TO THOSE AREAS IN WHICH WORK IS EXPECTED TO BE UNDER TAKEN DURING THE PROCEEDING 15 DAYS AND THAT CAN BE MULCHED IN ONE DAY PRIOR TO ANY SNOW EVENT. ALL AREAS SHALL BE CONSIDERED TO BE DENUDED UNTIL THE SUBBASE GRAVEL IS INSTALLED IN ROADWAY/PARKING AREAS OR THE AREAS

WINTER EXCAVATION AND EARTHWORK SHALL BE COMPLETED SUCH THAT ANY AREA LEFT EXPOSED CAN BE CONTROLLED BY THE

OF FUTURE LOAM AND SEED HAVE BEEN LOAMED, SEEDED AND MULCHED. HAY AND STRAW MULCH RATE SHALL BE A MINIMUM OF 150 LBS./1,000 S.F. (3 TONS/ACRE) AND SHALL BE PROPERLY ANCHORED. THE CONTRACTOR SHALL INSTALL ANY ADDED MEASURES WHICH MAY BE NECESSARY TO CONTROL EROSION/SEDIMENTATION FROM THE SITE DEPENDENT UPON THE ACTUAL SITE AND WEATHER CONDITIONS. CONTINUATION OF EARTHWORK OPERATIONS ON ADDITIONAL AREAS SHALL NOT

I. SOIL STOCKPILES STOCKPILES OF SOIL OR SUBSOIL SHALL BE MULCHED FOR OVER WINTER PROTECTION WITH HAY OR STRAW AT TWICE THE NORMAL RATE OR AT 150 LBS/1,000 S.F. (3 TONS PER ACRE) OR WITH A FOUR-INCH LAYER OF WOODWASTE EROSION CONTROL MIX. THIS SHALL BE DONE WITHIN 24 HOURS OF STOCKING AND RE-ESTABLISHED PRIOR TO ANY RAINFALL OR SNOWFALL. ANY SOIL STOCKPILE SHALL NOT BE PLACED

BEGIN UNTIL THE EXPOSED SOIL SURFACE ON THE AREA BEING WORKED HAS BEEN STABILIZED, IN ORDER TO MINIMIZE AREAS WITHOUT

2. NATURAL RESOURCE PROTECTION ANY AREAS WITHIN 100 FEET FROM ANY NATURAL RESOURCES. IF NOT STABILIZED WITH A MINIMUM OF 75% MATURE VEGETATION CATCH. SHALL BE MULCHED BY DECEMBER 1 AND ANCHORED WITH PLASTIC NETTING OR PROTECTED WITH EROSION CONTROL MATS. DURING WINTER CONSTRUCTION, A DOUBLE LINE OF SEDIMENT BARRIERS (I.E. SILT FENCE BACKED WITH HAY BALES OR EROSION CONTROL MIX) SHALL BE PLACED BETWEEN ANY NATURAL RESOURCE AND THE DISTURBED AREA. PROJECTS CROSSING THE NATURAL RESOURCE SHALL BE PROTECTED A MINIMUM DISTANCE OF 100 FEET ON EITHER SIDE FROM THE RESOURCE. EXISTING PROJECTS NOT STABILIZED BY DECEMBER 1 SHALL BE

PROTECTED WITH THE SECOND LINE OF SEDIMENT BARRIER TO ENSURE FUNCTIONALITY DURING THE SPRING THAW AND RAINS. DURING FROZEN CONDITIONS, SEDIMENT BARRIERS SHALL CONSIST OF WOODWASTE FILTER BERMS AS FROZEN SOIL PREVENTS THE PROPER

INSTALLATION OF HAY BALES AND SEDIMENT SILT FENCES. AN AREA SHALL BE CONSIDERED DENUDED UNTIL AREAS OF FUTURE LOAM AND SEED HAVE BEEN LOAMED, SEEDED AND MULCHED. HAY AND

STRAW MULCH SHALL BE APPLIED AT A RATE OF 150 LB. PER 1,000 SQUARE FEET OR 3 TONS/ACRE (TWICE THE NORMAL ACCEPTED RATE OF 75-LBS./1,000 S.F. OR 1.5 TONS/ACRE) AND SHALL BE PROPERLY ANCHORED. MULCH SHALL NOT BE SPREAD ON TOP OF SNOW. THE SNOW SHALL BE REMOVED DOWN TO A ONE—INCH DEPTH OR LESS PRIOR TO APPLICATION. AFTER EACH DAY OF FINAL GRADING. THE AREA SHALL BE PROPERLY STABILIZED WITH ANCHORED HAY OR STRAW OR EROSION CONTROL MATTING. AN AREA SHALL BE CONSIDERED TO HAVE BEEN STABILIZED WHEN EXPOSED SURFACES HAVE BEEN EITHER MULCHED WITH STRAW OR HAY AT A RATE OF 150 LB. PER 1,000 SQUARE FEET (3 TONS/ACRE) AND ADEQUATELY ANCHORED THAT GROUND SURFACE IS NOT VISIBLE THOUGH THE MULCH.

BETWEEN THE DATES OF NOVEMBER 1 AND APRIL 15, ALL MULCH SHALL BE ANCHORED BY PEG LINE, MULCH NETTING, ASPHALT EMULSION CHEMICAL, OR WOOD CELLULOSE FIBER. WHEN GROUND SURFACE IS NOT VISIBLE THROUGH THE MULCH THEN COVER IS SUFFICIENT. AFTER NOVEMBER 1ST/, MULCH AND ANCHORING OF ALL BARE SOIL SHALL OCCUR AT THE END OF EACH FINAL GRADING WORKDAY.

5. MULCHING ON SLOPES AND DITCHES SLOPES SHALL NOT BE LEFT EXPOSED FOR ANY EXTENDED TIME OF WORK SUSPENSION UNLESS FULLY MULCHED AND ANCHORED WITH PEG AND NETTING OR WITH EROSION CONTROL BLANKETS. MULCHING SHALL BE APPLIED AT A RATE OF 230 LBS/1,000 S.F. ON ALL SLOPES GREATER THAN 8%.

MULCH NETTING SHALL BE USED TO ANCHOR MULCH IN ALL DRAINAGE WAYS WITH A SLOPE GREATER THAN 3% FOR SLOPES EXPOSED TO DIRECT WINDS AND FOR ALL OTHER SLOPES GREATER THAT 8%. EROSION CONTROL BLANKETS SHALL BE USED IN LIEU OF MULCH IN ALL DRAINAGE WAYS WITH SLOPES GREATER THAN 8%. EROSION CONTROL MIX CAN BE USED TO SUBSTITUTE EROSION CONTROL BLANKETS ON ALL SLOPES EXCEPT DITCHES.

SFFDING BETWEEN THE DATES OF OCTOBER 15 AND APRIL 1ST/, LOAM OR SEED WILL NOT BE REQUIRED. DURING PERIODS OF ABOVE FREEZING TEMPERATURES FINISHED AREAS SHALL BE FINE GRADED AND EITHER PROTECTED WITH MULCH OR TEMPORARILY SEEDED AND MULCHED UNTIL SUCH TIME AS THE FINAL TREATMENT CAN BE APPLIED. IF THE DATE IS AFTER NOVEMBER 1ST/ AND IF THE EXPOSED AREA HAS BEEN LOAMED, FINAL GRADED WITH A UNIFORM SURFACE, THEN THE AREA MAY BE DORMANT SEEDED AT A RATE OF 3 TIMES HIGHER THAN SPECIFIED FOR PERMANENT SEED AND THEN MULCHED. DORMANT SEEDING MAY BE SELECTED TO BE PLACED PRIOR TO THE PLACEMENT OF MULCH AND FABRIC NETTING ANCHORED WITH STAPLES. IF DORMANT SEEDING IS USED FOR THE SITE, ALL DISTURBED AREAS SHALL RECEIVE 4"OF LOAM AND SEED AT AN APPLICATION RATE OF 5 LBS/1,000 S.F. ALL AREAS SEEDED DURING THE WINTER SHALL BE INSPECTED IN THE SPRING FOR ADEQUATE CATCH. ALL AREAS INSUFFICIENTLY VEGETATED (LESS THAN 75% CATCH) SHALL BE REVEGETATED BY REPLACING LOAM, SEED AND MULCH. IF DORMANT SEEDING IS NOT USED FOR THE SITE, ALL DISTURBED AREAS SHALL BE REVEGETATED IN THE SPRING.

STANDARDS FOR TIMELY STABILIZATION OF CONSTRUCTION SITES DURING WINTER

1. STANDARD FOR THE TIMELY STABILIZATION OF DITCHES AND CHANNELS -- THE APPLICANT SHALL CONSTRUCT AND STABILIZE ALL STONE-LINED DITCHES AND CHANNELS ON THE SITE BY NOVEMBER 15. THE APPLICANT SHALL CONSTRUCT AND STABILIZE ALL GRASS-LINED DITCHES AND CHANNELS ON THE SITE BY SEPTEMBER 1. IF THE APPLICANT FAILS TO STABILIZE A DITCH OR CHANNEL TO BE GRASS-LINED BY SEPTEMBER 1, THEN THE APPLICANT WILL TAKE ONE OF THE FOLLOWING ACTIONS TO STABILIZE THE DITCH FOR LATE FALL AND WINTER.

INSTALL A SOD LINING IN THE DITCH -- THE APPLICANT SHALL LINE THE DITCH WITH PROPERLY INSTALLED SOD BY OCTOBER 1. PROPER INSTALLATION INCLUDES THE APPLICANT PINNING THE SOD ONTO THE SOIL WITH WIRE PINS, ROLLING THE SOD TO GUARANTEE CONTACT BETWEEN THE SOD AND UNDERLYING SOIL, WATERING THE SOD TO PROMOTE ROOT GROWTH INTO THE DISTURBED SOIL, AND ANCHORING THE SOD WITH JUTE OR PLASTIC MESH TO PREVENT THE SOD STRIPS FROM SLOUGHING DURING FLOW CONDITIONS.

INSTALL A STONE LINING IN THE DITCH --THE APPLICANT SHALL LINE THE DITCH WITH STONE RIPRAP BY NOVEMBER 15. THE APPLICANT SHALL HIRE A REGISTERED PROFESSIONAL ENGINEER TO DETERMINE THE STONE SIZE AND LINING THICKNESS NEEDED TO WITHSTAND THE ANTICIPATED FLOW VELOCITIES AND FLOW DEPTHS WITHIN THE DITCH. IF NECESSARY, THE APPLICANT SHALL REGRADE THE DITCH PRIOR TO PLACING THE STONE LINING SO TO PREVENT THE STONE LINING FROM REDUCING THE DITCH'S CROSS-SECTIONAL AREA.

STANDARD FOR THE TIMELY STABILIZATION OF DISTURBED SLOPES -- THE APPLICANT SHALL CONSTRUCT AND STABILIZE STONE-COVERED SLOPES BY NOVEMBER 15. THE APPLICANT SHALL SEED AND MULCH ALL SLOPES TO BE VEGETATED BY SEPTEMBER 1 THE DEPARTMENT SHALL CONSIDER ANY AREA HAVING A GRADE GREATER THAN 15% TO BE A SLOPE. IF THE APPLICANT FAILS TO STABILIZE ANY SLOPE TO BE VEGETATED BY SEPTEMBER 1, THEN THE APPLICANT SHALL TAKE ONE OF THE FOLLOWING ACTIONS TO STABILIZE THE SLOPE FOR LATE FALL AND WINTER.

STABILIZE THE SOIL WITH TEMPORARY VEGETATION AND EROSION CONTROL MATS -- BY SEPTEMBER 1 THE APPLICANT SHALL SEED THE DISTURBED SLOPE WITH WINTER RYE AT A SEEDING RATE OF 3 POUNDS PER 1,000 SQUARE FEET AND APPLY EROSION CONTROL MATS OVER THE MULCHED SLOPE. THE APPLICANT SHALL MONITOR GROWTH OF THE RYE OVER THE NEXT 30 DAYS. IF THE RYE FAILS TO GROW AT LEAST THREE INCHES OR COVER AT LEAST 75% OF THE DISTURBED SLOPE BY NOVEMBER 1, THEN THE APPLICANT SHALL COVER THE SLOPE WITH A LAYER OF WOODWASTE COMPOST AS DESCRIBED IN ITEM III OF THIS STANDARD OR WITH STONE RIPRAP AS DESCRIBED IN ITEM IV OF

STABILIZE THE SLOPE WITH SOD -- THE APPLICANT SHALL STABILIZE THE DISTURBED SLOPE WITH PROPERLY INSTALLED SOD BY SEPTEMBER . PROPER INSTALLATION INCLUDES THE APPLICANT PINNING THE SOD ONTO THE SLOPE WITH WIRE PINS, ROLLING THE SOD TO GUARANTEE CONTACT BETWEEN THE SOD AND UNDERLYING SOIL, AND WATERING THE SOD TO PROMOTE ROOT GROWTH INTO THE DISTURBED SOIL. THE APPLICANT SHALL NOT USE LATE-SEASON SOD INSTALLATION TO STABILIZE SLOPES HAVING A GRADE GREATER THAN 33% (3H:1V).

STABILIZE THE SLOPE WITH WOODWASTE COMPOST -- THE APPLICANT SHALL PLACE A SIX-INCH LAYER OF WOODWASTE COMPOST ON THE SLOPE BY NOVEMBER 15. PRIOR TO PLACING THE WOODWASTE COMPOST, THE APPLICANT SHALL REMOVE ANY SNOW ACCUMULATION ON THE DISTURBED SLOPE. THE APPLICANT SHALL NOT USE WOODWASTE COMPOST TO STABILIZE SLOPES HAVING GRADES GREATER THAN 50% (2H:1V) OR HAVING GROUNDWATER SEEPS ON THE SLOPE FACE.

STABILIZE THE SLOPE WITH STONE RIPRAP -- THE APPLICANT SHALL PLACE A LAYER OF STONE RIPRAP ON THE SLOPE BY NOVEMBER 15. THE APPLICANT SHALL HIRE A REGISTERED PROFESSIONAL ENGINEER TO DETERMINE THE STONE SIZE NEEDED FOR STABILITY AND TO DESIGN A FILTER LAYER FOR UNDERNEATH THE RIPRAP.

3. STANDARD FOR THE TIMELY STABILIZATION OF DISTURBED SOILS —— BY SEPTEMBER 15 THE APPLICANT SHALL SEED AND MULCH ALL DISTURBED SOILS ON AREAS HAVING A SLOPE LESS THAN 15%. IF THE APPLICANT FAILS TO STABILIZE THESE SOILS BY THIS DATE, THEN THE APPLICANT SHALL TAKE ONE OF THE FOLLOWING ACTIONS TO STABILIZE THE SOIL FOR LATE FALL AND WINTER.

STABILIZE THE SOIL WITH TEMPORARY VEGETATION -- BY SEPTEMBER 1 THE APPLICANT SHALL SEED THE DISTURBED SOIL WITH WINTER RYE AT A SEEDING RATE OF 3 POUNDS PER 1000 SQUARE FEET, LIGHTLY MULCH THE SEEDED SOIL WITH HAY OR STRAW AT 75 POUNDS PER 1000 SQUARE FEET, AND ANCHOR THE MULCH WITH PLASTIC NETTING. THE APPLICANT SHALL MONITOR GROWTH OF THE RYE OVER THE NEXT 30 DAYS. IF THE RYE FAILS TO GROW AT LEAST THREE INCHES OR COVER AT LEAST 75% OF THE DISTURBED SOIL BEFORE NOVEMBER 1, THEN THE APPLICANT SHALL MULCH THE AREA FOR OVER-WINTER PROTECTION AS DESCRIBED BELOW.

STABILIZE THE SOIL WITH SOD -- THE APPLICANT SHALL STABILIZE THE DISTURBED SOIL WITH PROPERLY INSTALLED SOD BY SEPTEMBER 15. PROPER INSTALLATION INCLUDES THE APPLICANT PINNING THE SOD ONTO THE SOIL WITH WIRE PINS, ROLLING THE SOD TO GUARANTEE CONTACT BETWEEN THE SOD AND UNDERLYING SOIL, AND WATERING THE SOD TO PROMOTE ROOT GROWTH INTO THE DISTURBED SOIL.

STABILIZE THE SOIL WITH MULCH -- BY NOVEMBER 15 THE APPLICANT SHALL MULCH THE DISTURBED SOIL BY SPREADING HAY OR STRAW AT A RATE OF AT LEAST 150 POUNDS PER 1000 SQUARE FEET ON THE AREA SO THAT NO SOIL IS VISIBLE THROUGH THE MULCH. PRIOR TO APPLYING THE MULCH. THE APPLICANT SHALL REMOVE ANY SNOW ACCUMULATION ON THE DISTURBED AREA. IMMEDIATELY AFTER APPLYING THE MULCH, THE APPLICANT WILL ANCHOR THE MULCH WITH PLASTIC NETTING TO PREVENT WIND FROM MOVING THE MULCH OFF THE DISTURBED SOIL.

1.8 MAINTENANCE OF FACILITIES

THE STORMWATER FACILITIES WILL BE MAINTAINED BY THE APPLICANT, THE CITY OF LEWISTON OR THEIR ASSIGNED HEIRS. THE CONTRACT DOCUMENTS WILL REQUIRE THE CONTRACTOR TO DESIGNATE A PERSON RESPONSIBLE FOR MAINTENANCE OF THE SEDIMENTATION CONTROL FEATURES DURING CONSTRUCTION AS REQUIRED BY THE EROSION CONTROL REPORT. LONG-TERM OPERATION/MAINTENANCE RECOMMENDED FOR THE STORMWATER FACILITIES IS PRESENTED BELOW AND WITHIN THE OPERATION AND MAINTENANCE MANUAL.

THE RESPONSIBLE PARTY MAY CONTRACT WITH SUCH PROFESSIONALS, AS MAY BE NECESSARY IN ORDER TO COMPLY WITH THIS PROVISION AND MAY RELY ON THE ADVICE OF SUCH PROFESSIONALS IN CARRYING OUT ITS DUTY HEREUNDER, PROVIDED, THAT THE FOLLOWING OPERATION AND MAINTENANCE PROCEDURES ARE HEREBY ESTABLISHED AS A MINIMUM FOR COMPLIANCE WITH THIS SECTION. A MAINTENANCE LOG OF THE INSPECTIONS SHALL BE KEPT BY THE RESPONSIBLE PARTY.

INSPECTION AND MAINTENANCE FREQUENCY AND CORRECTIVE MEASURES: THE FOLLOWING AREAS, FACILITIES, AND MEASURES WILL BE INSPECTED AND THE IDENTIFIED DEFICIENCIES WILL BE CORRECTED. CLEAN-OUT MUST INCLUDE THE REMOVAL AND LEGAL DISPOSAL OF ANY ACCUMULATED SEDIMENTS AND DEBRIS.

ROADWAYS AND PARKING SURFACES: CLEAR ACCUMULATIONS OF WINTER SAND IN PARKING LOTS AND ALONG ROADWAYS AT LEAST ONCE A YEAR, PREFERABLY IN THE SPRING. ACCUMULATIONS ON PAVEMENT MAY BE REMOVED BY PAVEMENT SWEEPING. ACCUMULATIONS OF SAND ALONG ROAD SHOULDERS MAY BE REMOVED BY GRADING EXCESS SAND TO THE PAVEMENT EDGE AND REMOVING IT MANUALLY OR BY A FRONT-END LOADER. REPAIR POTHOLES AND OTHER ROADWAY OBSTRUCTIONS AND HAZARDS. PLOWING AND SANDING OF PAVED AREAS SHALL BE PERFORMED AS NECESSARY TO MAINTAIN VEHICULAR TRAFFIC SAFETY.

CATCH BASINS:

INSPECT CATCH BASINS 2 TIMES PER YEAR (PREFERABLY IN SPRING AND FALL) TO ENSURE THAT THE CATCH BASINS ARE WORKING IN THEIR INTENDED FASHION AND THAT THEY ARE FREE OF DEBRIS. CLEAN STRUCTURES WHEN SEDIMENT DEPTHS REACH 12" FROM INVERT OF OUTLET. IF THE BASIN OUTLET IS DESIGNED WITH A HOOD TO TRAP FLOATABLE MATERIALS (I.E. SNOUT), CHECK TO ENSURE WATERTIGHT SEAL IS WORKING. AT A MINIMUM, REMOVE FLOATING DEBRIS AND HYDROCARBONS AT THE TIME OF THE INSPECTION.

INSPECT CULVERTS 2 TIMES PER YEAR (PREFERABLY IN SPRING AND FALL) TO ENSURE THAT THE CULVERTS ARE WORKING IN THEIR

INTENDED FASHION AND THAT THEY ARE FREE OF DEBRIS. REMOVE ANY OBSTRUCTIONS TO FLOW; REMOVE ACCUMULATED SEDIMENTS AND DEBRIS AT THE INLET. AT THE OUTLET, AND WITHIN THE CONDUIT AND REPAIR ANY EROSION DAMAGE AT THE CULVERT'S INLET AND OUTLET. THE DRIP STRIP WILL BE INSPECTED WITHIN THE FIRST THREE MONTHS AFTER CONSTRUCTION; THEREAFTER THE FILTER WILL BE INSPECTED 2

TIMES PER YEAR (PREFERABLY IN SPRING AND FALL) TO ENSURE THAT THE FILTER IS DRAINING WITHIN 24 TO 48 HOURS OF A RAIN EVENT EQUIVALENT TO 1"OR MORE. FAILURE TO DRAIN IN 72 HOURS WILL REQUIRE PART OR ALL OF THE SOIL FILTER MEDIA TO BE REMOVED AND REPLACED WITH NEW MATERIAL MEETING THE SOIL FILTER GRADATION. THE FACILITIES WILL BE INSPECTED AFTER MAJOR STORMS AND ANY IDENTIFIED DEFICIENCIES WILL BE CORRECTED, INSPECT FOR UNWANTED OR INVASIVE PLANTS AND REMOVE AS NECESSARY. REMOVE DEBRIS FROM THE SURFACE. SINCE THE ROOFLINE DRIP EDGE IS A PART OF THE APPROVED STORMWATER MANAGEMENT PLAN, IT CANNOT BE PAVED OVER OR ALTERED IN ANY WAY. GUTTERS SHALL NOT BE INSTALLED ALONG THE ROOFLINE.

INSPECT SLOPES AND EMBANKMENTS EARLY IN THE GROWING SEASON TO IDENTIFY ACTIVE OR POTENTIAL EROSION PROBLEMS. REPLANT BARE AREAS OR AREAS WITH SPARSE GROWTH. WHERE RILL EROSION IS EVIDENT, ARMOR THE AREA WITH AN APPROPRIATE LINING OR DIVERT THE EROSIVE FLOWS TO ON-SITE AREAS ABLE TO WITHSTAND THE CONCENTRATED FLOWS. THE FACILITIES WILL BE INSPECTED AFTER MAJOR STORMS AND ANY IDENTIFIED DEFICIENCIES WILL BE CORRECTED.

DITCHES, SWALES AND OTHER OPEN STORMWATER CHANNELS:

INSPECT 2 TIMES PER YEAR (PREFERABLY IN SPRING AND FALL) TO ENSURE THEY ARE WORKING IN THEIR INTENDED FASHION AND THAT THEY ARE FREE OF SEDIMENT AND DEBRIS. REMOVE ANY OBSTRUCTIONS TO FLOW, INCLUDING ACCUMULATED SEDIMENTS AND DEBRIS AND VEGETATED GROWTH. REPAIR ANY EROSION OF THE DITCH LINING. VEGETATED DITCHES WILL BE MOWED AT LEAST ANNUALLY OR OTHERWISE MAINTAINED TO CONTROL THE GROWTH OF WOODY VEGETATION AND MAINTAIN FLOW CAPACITY. ANY WOODY VEGETATION GROWING THROUGH RIPRAP LININGS MUST ALSO BE REMOVED. REPAIR ANY SLUMPING SIDE SLOPES AS SOON AS PRACTICABLE. IF THE DITCH HAS A RIPRAP LINING, REPLACE RIPRAP ON AREAS WHERE ANY UNDERLYING FILTER FABRIC OR UNDERDRAIN GRAVEL IS SHOWING THROUGH THE STONE OR WHERE STONES HAVE DISLODGED. CORRECT ANY EROSION OF THE CHANNEL'S BOTTOM OR SIDESLOPES. THE FACILITIES SHALL BE INSPECTED AFTER MAJOR STORMS AND ANY IDENTIFIED DEFICIENCIES SHALL BE CORRECTED.

POST CONSTRUCTION STORMWATER MANAGEMENT

THE PROJECT IS SUBJECT TO THE POST CONSTRUCTION STORMWATER MANAGEMENT PROVISIONS CONTAINED IN THE CITY OF LEWISTON ZONING AND LAND USE CODE ARTICLE XIII SECTION 15. THE FOLLOWING ARE REQUIRED UNDER THE ORDINANCE.

i) A QUALIFIED POST CONSTRUCTION THIRD PARTY INSPECTOR SHALL, AT LEAST ANNUALLY, INSPECT THE STORMWATER MANAGEMENT FÁCILITIES, INCLUDING BUT NOT LIMITED TO ANY PARKING AREAS, CATCH BASINS, DRAINAGE SWALES, DETENTION BASINS AND PONDS, PIPES AND RELATED STRUCTURES, IN ACCORDANCE WITH ALL MUNICIPAL AND STATE INSPECTION, CLEANING AND MAINTENANCE REQUIREMENTS OF THE APPROVED POST-CONSTRUCTION STORMWATER MANAGEMENT PLAN. b) IF THE STORMWATER MANAGEMENT FACILITIES REQUIRE MAINTENANCE TO FUNCTION AS INTENDED BY THE APPROVED

POST-CONSTRUCTION STORMWATER MANAGEMENT PLAN, THAT PERSON SHALL TAKE CORRECTIVE ACTION(S) TO ADDRESS THE DEFICIENCY OR

DEFICIENCIES. c) A QUALIFIED POST CONSTRUCTION THIRD-PARTY INSPECTOR SHALL PROVIDE, ON OR BY MAY 31 OF EACH YEAR, A COMPLETED AND SIGNED CERTIFICATION TO THE ENFORCEMENT AUTHORITY IN A FORM IDENTICAL TO THE CITY OF LEWISTON'S ANNUAL STORMWATER MANAGEMENT FACILITIES CERTIFICATION FORM, CERTIFYING THAT THE STORMWATER MANAGEMENT FACILITIES HAVE BEEN INSPECTED, AND THAT THEY ARE ADEQUATELY MAINTAINED AND FUNCTIONING AS INTENDED BY THE APPROVED POST—CONSTRUCTION STORMWATER MANAGEMENT PLAN, OR THAT THEY REQUIRE MAINTENANCE OR REPAIR, DESCRIBING ANY REQUIRED MAINTENANCE AND ANY DEFICIENCIES FOUND DURING INSPECTION OF THE STORMWATER MANAGEMENT FACILITIES AND, IF THE STORMWATER MANAGEMENT FACILITIES REQUIRE MAINTENANCE OR REPAIR OF DEFICIENCIES IN ORDER TO FUNCTION AS INTENDED BY THE APPROVED POST-CONSTRUCTION STORMWATER MANAGEMENT PLAN, THE PERSON SHALL PROVIDE A RECORD OF THE REQUIRED MAINTENANCE OR DEFICIENCY AND CORRECTIVE ACTION(S) TAKEN.

AS PART OF THE SITE PLAN PERMIT, THE APPLICANT IS REQUIRED TO MEET THE STANDARDS IN APPENDIX C OF THE MDEP CHAPTER 500 RULES. THE FOLLOWING PROCEDURES ARE HEREBY ESTABLISHED AS A MINIMUM FOR COMPLIANCE WITH THIS SECTION. FOR FURTHER INFORMATION ON THE PROCEDURES LISTED BELOW, REFER TO CHAPTER 500 RULES - APPENDIX C.

CONTROLS MUST BE USED TO PREVENT POLLUTANTS FROM CONSTRUCTION AND WASTE MATERIALS STORED ON SITE TO ENTER STORMWATER, WHICH INCLUDES STORAGE PRACTICES TO MINIMIZE EXPOSURE OF THE MATERIALS TO STORMWATER. THE SITE CONTRACTOR OR OPERATOR MUST DEVELOP, AND IMPLEMENT AS NECESSARY, APPROPRIATE SPILL PREVENTION, CONTAINMENT, AND RESPONSE PLANNING MEASURES.

DURING CONSTRUCTION, LIQUID PETROLEUM PRODUCTS AND OTHER HAZARDOUS MATERIALS WITH THE POTENTIAL TO CONTAMINATE GROUNDWATER MAY NOT BE STORED OR HANDLED IN AREAS OF THE SITE DRAINING TO AN INFILTRATION AREA. AN "INFILTRATION AREA" IS ANY AREA OF THE SITE THAT BY DESIGN OR AS A RESULT OF SOILS, TOPOGRAPHY AND OTHER RELEVANT FACTORS ACCUMULATES RUNOFF THAT INFILTRATES INTO THE SOIL. DIKES, BERMS, SUMPS, AND OTHER FORMS OF SECONDAR' CONTAINMENT THAT PREVENT DISCHARGE TO GROUNDWATER MAY BE USED TO ISOLATE PORTIONS OF THE SITE FOR THE PURPOSES OF STORAGE AND HANDLING OF THESE MATERIALS. ANY PROJECT PROPOSING INFILTRATION OF STORMWATER MUST PROVIDE ADEQUATE PRE-TREATMENT OF STORMWATER PRIOR TO DISCHARGE OF STORMWATER TO THE INFILTRATION AREA, OR PROVIDE FOR TREATMENT WITHIN THE INFILTRATION AREA, IN ORDER TO PREVENT THE ACCUMULATION OF FINES, REDUCTION IN INFILTRATION RATE, AND CONSEQUENT FLOODING AND DESTABILIZATION.

ACTIONS MUST BE TAKEN TO ENSURE THAT ACTIVITIES DO NOT RESULT IN NOTICEABLE

EROSION OF SOILS OR FUGITIVE DUST EMISSIONS DURING OR AFTER CONSTRUCTION. OIL MAY NOT BE USED FOR DUST CONTROL, BUT OTHER WATER ADDITIVES MAY BE CONSIDERED AS NEEDED. A STABILIZED CONSTRUCTION ENTRANCE (SCE) SHOULD BE INCLUDED TO MINIMIZE TRACKING OF MUD AND SEDIMENT. IF OFF-SITE TRACKING OCCURS, PUBLIC ROADS SHOULD BE SWEPT IMMEDIATELY AND NO LESS THAN ONCE A WEEK AND PRIOR TO SIGNIFICANT STORM EVENTS. OPERATIONS DURING DRY MONTHS, THAT EXPERIENCE FUGITIVE DUST PROBLEMS, SHOULD WET DOWN UNPAVED ACCESS ROADS ONCE A WEEK OR MORE FREQUENTLY AS NEEDED WITH A WATER ADDITIVE TO SUPPRESS FUGITIVE SEDIMENT AND DUST.

DEBRIS AND OTHER MATERIALS:

MINIMIZE THE EXPOSURE OF CONSTRUCTION DEBRIS, BUILDING AND LANDSCAPING MATERIALS, TRASH, FERTILIZERS, PESTICIDES, HERBICIDES, DETERGENTS, SANITARY WASTE AND OTHER MATERIALS TO PRECIPITATION AND STORMWATER RUNOFF. THESE MATERIALS MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE.

TRENCH OR FOUNDATION DE-WATERING: EXCAVATION DE-WATERING IS THE REMOVAL OF WATER FROM TRENCHES FOUNDATIONS, COFFER DAMS, PONDS, AND OTHER AREAS WITHIN THE CONSTRUCTION AREA THAT RETAIN WATER AFTER EXCAVATION. IN MOST CASES THE COLLECTED WATER IS HEAVILY SILTED AND HINDERS CORRECT AND SAFE CONSTRUCTION PRACTICES. THE COLLECTED WATER REMOVED FROM THE PONDED AREA, EITHER THROUGH GRAVITY OR PUMPING, MUST BE SPREAD THROUGH NATURAL WOODED BUFFERS OR REMOVED TO AREAS THAT ARE SPECIFICALLY DESIGNED TO COLLECT THE MAXIMUM AMOUNT OF SEDIMENT POSSIBLE, LIKE A COFFERDAM SEDIMENTATION BASIN.

AUTHORIZED NON-STORMWATER DISCHARGES: IDENTIFY AND PREVENT CONTAMINATION BY NON-STORMWATER DISCHARGES. WHERE ALLOWED NON-STORMWATER DISCHARGES EXIST, THEY MUST BE IDENTIFIED AND STEPS SHOULD BE TAKEN TO ENSURE THE IMPLEMENTATION OF APPROPRIATE POLLUTION PREVENTION MEASURES FOR THE NON-STORMWATER COMPONENT(S) OF THE DISCHARGE. AUTHORIZED NON-STORMWATER DISCHARGES ARE:

AVOID ALLOWING THE WATER TO FLOW OVER DISTURBED AREAS OF THE SITE.

- (a) DISCHARGES FROM FIREFIGHTING ACTIVITY;
- (b) FIRE HYDRANT FLUSHINGS;
- (c) VEHICLE WASHWATER IF DETERGENTS ARE NOT USED AND WASHING IS LIMITED TO THE EXTERIOR OF VEHICLES (ENGINE, UNDERCARRIAGE AND TRANSMISSION WASHING IS PROHIBITED);
- (d) DUST CONTROL RUNOFF IN ACCORDANCE WITH PERMIT CONDITIONS AND APPENDIX

(e) ROUTINE EXTERNAL BUILDING WASHDOWN, NOT INCLUDING SURFACE PAINT REMOVAL, THAT DOES NOT INVOLVE DETERGENTS;

(f) PAVEMENT WASHWATER (WHERE SPILLS/LEAKS OF TOXIC OR HAZARDOUS MATERIALS HAVE NOT OCCURRED, UNLESS ALL SPILLED MATERIAL HAD BEEN REMOVED) IF DETERGENTS ARE NOT USED:

- (g) UNCONTAMINATED AIR CONDITIONING OR COMPRESSOR CONDENSATE;
- (h) UNCONTAMINATED GROUNDWATER OR SPRING WATER;
- (i) FOUNDATION OR FOOTER DRAIN-WATER WHERE FLOWS ARE NOT CONTAMINATED; (j) UNCONTAMINATED EXCAVATION DEWATERING (SEE REQUIREMENTS IN APPENDIX
- (k) POTABLE WATER SOURCES INCLUDING WATERLINE FLUSHINGS; /AND
- (I) LANDSCAPE IRRIGATION.

OPERATION AND MAINTENANCE:

UNAUTHORIZED NON-STORMWATER DISCHARGES: IDENTIFY AND PREVENT CONTAMINATION BY NON-STORMWATER DISCHARGES. SPECIFICALLY, THE DEPARTMENT'S APPROVAL DOES NOT AUTHORIZE DISCHARGES OF

) WASTEWATER FROM THE WASHOUT OR CLEANOUT OF CONCRETE, STUCCO, PAINT, FORM RELEASE OILS, CURING COMPOUNDS OR OTHER CONSTRUCTION MATERIALS;

(c) SOAPS, SOLVENTS, OR DETERGENTS USED IN VEHICLE AND EQUIPMENT WASHING;


TOXIC OR HAZARDOUS SUBSTANCES FROM A SPILL OR OTHER RELEASE.

b) FUELS, OILS OR OTHER POLLUTANTS USED IN VEHICLE AND EQUIPMENT

NOTE: THIS PLAN SET IS ISSUED FOR PERMITTING PURPOSES AND SHALL NOT BE USED FOR CONSTRUCTION.

8 8					
<					
-SR					
Ë					
ORA					
GPST(PEF	RMITTING
/ G	Rev.	Date	Revision	lss	sued Fo

PERMITTING	4/4/25	RJB
Issued For	4/4/25 Date	Ву





Drawing Name:	Erosion Control Notes	
Project:	Bath Fire Headquarters 826 High Street, Bath, ME 04530	
Client:	Context Architecture 65 Franklin Street, Boston , MA 02110	


Drawing No.














BAT 864 Scale: Drawn by: K.MAGGIO Date 04.07.2025

HEADQU/ ME 04530 ATH FIRE STATION F 34 HIGH STREET, BATH, N ect number: 2413.00


PE 1"=20'-0"

PLANTING SCHEDULE


	1					
SYMB.	QTY	BOT. NAME	COMMON NAME	SIZE	ROOT	COMMENTS
DECIDU	OUS TREES					
AR	5	ACER RUBRUM 'OCTOBER GLORY'	OCTOBER GLORY MAPLE	2.5-3" CAL.	В&В	SINGLE STEM, FULL HEAVY, MATCHED
ВР	3	BETULA PAPYRIFERA	PAPER BIRCH	10-12' HT	В&В	MULTI STEM, FULL, HEAVY, MATCHED
TA	8	TILIA AMERICANA	AMERICAN LINDEN	2.5-3" CAL.	B&B	SINGLE STEM, FULL HEAVY, MATCHED
EVERGR	EEN TREES					
PS	9	PINUS STROBUS	EASTERN WHITE PINE	2.5-3" CAL.	В&В	SINGLE STEM, FULL HEAVY, MATCHED
DECIDU	OUS SHRUB	S				
CS	36	CORNUS SERICEA	RED OSIER DOGWOOD	#5 CONT.	CONT.	PLANT 4' O.C.
RH	17	RHODODENDRON 'PJM'	PJM RHODODENDRON	#7 CONT.	CONT.	PLANT 4' O.C.
RM	13	ROSA 'MEIBENBINO'	PETITE KNOCKOUT ROSE	#3 CONT.	CONT.	PLANT 4' O.C.
ST	21	SPIRAEA NIPPONICA 'SNOWMOUND'	SNOWMOUND SPIREA	#5 CONT.	CONT.	PLANT 3' O.C.
SV	16	SYRINGA VULGARIS	LILAC	#5 CONT.	CONT.	PLANT 5' O.C.
VD	19	VIBURNUM DENTATUM	ARROWWOOD VIBURNUM	24-36" HT.	CONT.	PLANT 4' O.C.
EVERGR	EEN SHRUB	S				
IG	16	ILEX GLABRA 'SHAMRACK'	INKBERRY	#5 CONT.	CONT.	PLANT 4' O.C.
JC	7	JUNIPERUS CONFERTA 'BLUE PACIFIC'	SHORE JUNIPER	#3 CONT.	CONT.	PLANT 4' O.C.
PERENN	IALS					
НА	40	HEUCHERA AMERICANA	CORAL BELLS	#2 CONT.	CONT.	PLANT 1' O.C.
LM	165	LIRIOPE MUSCARI	BIG BLUE LILYTURF	#2 CONT.	CONT.	PLANT 1' O.C.
EP	40	ECHINACEA PURPUREA	PURPLE CONEFLOWER	#2 CONT.	CONT.	PLANT 2' O.C.
SEED M	X				!	
2,457 SY LAWN SEED MIX				ERNST CONSERVATION SEEDS: 8884 MERCER PIKE MEADVILLE, PA 16335 ITEM NUMBER:XXX		
MULCH		<u> </u>				
78 CY PLANTING AREAS MULCH SHALL BE A MINIMUM OF 3" FOR ALL PLANTING AREAS						
TREE PR	OTECTION	L				
	50 LF	TREES TO BE REMOVED), SEE CIVIL PLANS			
TREES T	O BE REMO	VED				
	20	TREES TO BE REMOVED	, SEE CIVIL PLANS			

PLANTING NOTES:

- 1. ALL NEW PLANT MATERIAL SHALL CONFORM TO THE REQUIREMENTS AS ESTABLISHED BY THE AMERICAN ASSOCIATION OF NURSERYMAN, LATEST EDITION. IN ADDITION, ALL NEW PLANT MATERIAL FOR THE PROJECT SHALL BE OF THE HIGHEST SPECIMEN QUALITY.
- 2. SEE SPECIFICATIONS FOR ITEMS NOT COVERED ON THE PLANS AND DETAILS.
- 3. CONTRACTOR SHALL INSPECT SITE PRIOR TO BEGINNING PLANTING OPERATIONS AND NOTIFY THE ENGINEER/LANDSCAPE ARCHITECT OF ANY CONDITIONS THAT ARE NOT SUITABLE TO PERFORMING PLANTING OPERATIONS. CONTRACTOR SHALL NOTIFY THE ENGINEER/LANDSCAPE ARCHITECT OF ANY CONDITIONS THAT WOULD PREVENT HEALTHY GROWTH OF PLANT MATERIAL. THIS INCLUDES PRESENCE OF PESTS AND/OR DISEASES ON EXISTING VEGETATION.
- 4. NO TREES SHALL BE PLANTED BEFORE ACCEPTANCE OF ROUGH GRADING. TREES SHALL BEAR SAME RELATIONSHIP TO FINISH
- GRADE AS THEY BORE TO PREVIOUS GRADE. 5. PLANT GROUPING AND LOCATIONS ARE DIAGRAMMATIC. THE LOCATION OF PLANTS SHALL BE APPROVED IN THE FIELD BY THE ENGINEER/LANDSCAPE ARCHITECT. PLANTS INSTALLED PRIOR TO FIELD STAKING OR DIRECTION BY THE ENGINEER/LANDSCAPE ARCHITECT SHALL BE REPLACED AS DIRECTED BY THE ENGINEER/LANDSCAPE ARCHITECT AT THE CONTRACTOR'S EXPENSE.
- 6. PLANT MATERIAL DELIVERED ON SITE SHALL BE HEALED-IN AT A SHADY LOCATION UNTIL PLANTING AREA IS PREPARED FOR INSTALLATION. ANY PLANTS REMAINING UNPLANTED ON THE SITE FOR MORE THAN 24 HOURS SHALL BE PROTECTED AND MAINTAINED INCLUDING BUT NOT LIMITED TO WATER AND SHADE. DAMAGED OR STRESSED PLANTS SHALL BE REPLACED AT THE
- 7. THERE WILL BE NO SUBSTITUTIONS OF PLANT MATERIAL WITHOUT PRIOR WRITTEN APPROVAL BY THE ENGINEER/LANDSCAPE ARCHITECT. ANY PROPOSED SUBSTITUTIONS OF PLANT SPECIES SHALL BE MADE WITH PLANTS OF EQUIVALENT OVERALL FORM HEIGHT, BRANCHING HABIT, FLOWER, LEAF, COLOR, FRUIT AND CULTURE ONLY AS APPROVED BY THE ENGINEER/LANDSCAPE ARCHITECT.
- 8. THE GENERAL CONTRACTOR SHALL SUPPLY ALL NEW PLANT MATERIAL IN QUANTITIES SUFFICIENT TO COMPLETE THE PLANTING SHOWN ON THE DRAWINGS.
- 9. THE CONTRACTOR SHALL MAINTAIN ALL PREPARED PLANTING AREAS FREE FROM DEBRIS. NO STORAGE OR STOCKPILING SHALL OCCUR ON PLANTING AREAS.
- 10. THE CONTRACTOR IS TO USE CARE DURING EXCAVATION AND PLANTING TO AVOID DISTURBING OR DAMAGING ANY ADJACENT CONSTRUCTION SUBSURFACE DRAINAGE OR UTILITIES. ANY DAMAGE RESULTING FROM THIS CONSTRUCTION WILL BE THE CONTRACTOR'S RESPONSIBILITY AND SHALL BE RESTORED AT HIS EXPENSE TO THE SATISFACTION OF THE OWNER.
- 11. STAKE LOCATION OF ALL PROPOSED PLANTING FOR APPROVAL BY THE ENGINEER/LANDSCAPE ARCHITECT PRIOR TO COMMENCEMENT OF PLANTING.
- 12. THE CONTRACTOR SHALL SUPPLY PLANT MATERIAL IN THE QUANTITIES INDICATED ON THE PLANS. FOR DISCREPANCIES BETWEEN
- THE PLANS AND THE PLANT SCHEDULE, THE PLAN QUANTITIES SHALL PREVAIL. 13. ALL PLANT MATERIAL IN CONTAINERS SHALL BE WELL ESTABLISHED ROOTED MATERIAL THAT OCCUPIES THE ENTIRE VOLUME OF
- SPECIFIED CONTAINER. 14. PLANTS WITH GIRDLING ROOTS SHALL BE REJECTED. CONTAINER GROWN PLANTS WITH TIGHT ROOT MASSES SHALL BE SCARIFIED
- PRIOR TO PLANTING. 15. THE TREE ROOT FLARE SHALL BE EXPOSED AND PLANTED EVEN WITH THE FINISH GRADE. PREPARE ALL TREE PITS WITH IMPROVED
- TOPSOIL TO A MINIMUM DEPTH AS SHOWN IN THE DETAIL.
- 16. ALL PLANT BEDS ARE TO RECEIVE THREE INCHES (3") OF SHREDDED BARK MULCH AS SPECIFIED. NO SEPARATE PAY ITEM FOR MULCH OR AND/OR FERTILIZER PACKETS. PAID FOR UNDER PLANTING ITEMS.
- 17. SEE SPECIFICATION FOR HOW TO AMEND TOPSOIL.




SHRUB PLANTING SCALE: NTS



1. ALL PLANTINGS ON CENTER, SEE PLANT SCHEDULE NOTES FOR SPACING. 2. PLACE MULCH LAYER PRIOR TO PLANTING GROUND COVER.


PERENNIAL/GROUNDCOVER PLANTING



1. APPLY ANTI-DESICCANT PRIOR TO PLANTING.


2. PIT SHOULD BE THREE TIMES DIAMETER OF ROOTBALL.

TREE INSTALLATION: MULTI-STEM



- 1. CRITICAL PROTECTION ZONE: THE AREA SURROUNDING A TREE WITHIN A CIRCLE DESCRIBED BY A RADIUS OF ONE FOOT FOR EACH INCH OF THE TREE TRUNK DIAMETER AT 54" ABOVE FINISHED GRADE. FOR GROUPS OF TREES, PLACE BARRICADES BETWEEN TREES AND CONSTRUCTION
- 2. TREE PROTECTION BARRICADES SHALL BE LOCATED TO PROTECT A MINIMUM OF 75% OF THE **CRITICAL PROTECTION ZONE.**
- 3. SEE PLANS FOR EXTENT OF BARRICADE TO BE INSTALLED. THERE ARE NO CONSTRUCTION ACTIVITIES ON PRIVATE PROPERTIES. BARRICADES SHALL NOT BE INSTALLED ON PRIVATE

TREE PROTECTION BARRICADE SCALE: NTS



TREE INSTALLATION: 10' AND TALLER


 Δ

IER

_

Drawn by: K.MAGGIO

Date 04.07.202



SING SEEDING THE CATUL FOR THE CATULE STATE WERE AND THE CATULE STATE WERE AND THE CATULE STATE WERE CONTRIBUTED IN THE CATULE STATE OF THE CATULE STATE STATE OF THE CATULE STATE S

BECHANIC

STATION HEADQUARTERS
EET, BATH, ME 04530

DE: AS NOTED


TRIC,

Scale: AS NOTED Drawn by: JLK

Drawn by. JLK

Do. Issue Date
Planning Board 04/07/25

F0.2





JARTER!

LIGH

HEADQU/ ME 04530 ATH FIRE STATION F 34 HIGH STREET, BATH, N ect number: 2413.00

TRIC

BAT 864 project r Scale: AS NOTED

Drawn by: JLK

Planning Board 04/07/25