# **Western Avenue Separation**

Public Informational Meeting

August 19, 2021

Lee Leiner, PE
Bath Public Works Director
Jan Wiegman, PE







#### **Presentation Overview**

Project Overview
Sewer Re-Lining
Academy/Cobb Sewer
Western Ave Storm Drain Separation
Construction Schedule
Thank You



## **Project Overview**



#### **Sewer Re-Lining**

- 5 Locations
- Trenchless Rehab of Sewer Lines
- Reduction in Infiltration
- Strengthens Pipe



#### **Academy/Cobb**

- Existing Sewer in Poor Condition
- Replacement Sewer
- New Easements



#### **Western Ave**

- Separation of 8 CB
- New Storm Drain
- Some Cross Country
- Within Existing Easements



## **Sewer Re-Lining**

- Re-Lining Existing Sewer Line with Resin Impregnated Fabric Liner
- Trenchless Restoration of Sewer Lines –I&I Reduction
- Pipe sizes ranging from 8" to 36" and a total of approx. 3,700 feet
- Five locations
  - Central Ave
  - Commercial Street
  - High Street
  - Seafarer Lane
  - Cross Country near Cottage Street




## **Sewer Re-Lining**














## **Academy Street/ Cobb Road Sewer Replacement**

#### **Project Summary**

- Existing Sewer Line is in poor condition and runs across Private Property
- New 18" line with portion between existing structures
- New Easements across Private Property
- From Academy Street to Lincoln Street
- Not a candidate for relining



## **Academy/Cobb Sewer Replacement**





## **Academy/Cobb Sewer Replacement**














#### **Project Summary**

- Eight Catch Basins on Western and Cottage currently drain to sewer
- Project will Install new Storm Drain that Collects the 8 CBs
- All new lines and structures are located within existing City Easements/ROW
- Ties into 2020 Separation Project on High Street Off Ramp












High Street Off Ramp



Cross Country Sewer











Cottage Street

















Western Ave

Cross Country Sewer Easement



#### **Contractor Selection**



- Project was Bid in June
- Awarded to St. Laurent & Sons
- Experienced Utility and Site Contractor
- Required to Complete the project by June 30, 2022



#### Construction - Tentative Schedule

October 2021

Nov. 2021

Dec. 2020

Feb 2022 March 2022 June 2022



Connect into High Street Off Ramp Start Sewer Re-Lining. Clear Easement Area Complete Sewer Re-Lining.

Start Cross Country Storm Drain Replacement Complete Cross Country Storm Drain Start Sewer and Storm Drain Work in Roadway Complete
Construction



# THANK YOU

